BRUHAT BANGALORE MAHANAGARA PALIKE
BYTARAYANPURA DIVISION

Name of Work: Package 2 Consists of 3 Works of Rs.1100.00 Lakhs

1.Improvements to roads and drains at Kogilu and surrounding area in Ward No 05 Byatarayanapura sub division.
2.Improvements to roads and drains at Agrahara and surrounding area in Ward No 05 Byatarayanapura sub division.
3.Improvements to roads and drains at Hegdenagar and surrounding area in Ward No 06 Byatarayanapura sub division.

MODIFIED ESTIMATE

TEJUS CONSULTANTS
CONSULTING ENGINEERS AND DESIGNERS
No.45, Present BBMP No.1204/45, Old No.1204, 1st Main,
MRCR Layout, Bangalore-560040
email: tejusconsultants@gmail.com

Bruhat Bengaluru Mahanagara Palike

Bytarayanapura Sub Division

Name of Project : - Package 2 Consists of 3 Works of Rs.1100.00 Lakhs

1.Improvements to roads and drains at Kogilu and surrounding area in Ward No 05 Byatarayanapura sub division

2.Improvements to roads and drains at Agrahara and surrounding area in Ward No 05 Byatarayanapura sub division

3.Improvements to roads and drains at Hegdenagar and surrounding area in Ward No 06 Byatarayanapura sub division

Name of Agency :- Benaka Developers & Project Pvt.Ltd.

Modified Estimate — **Estimate Cost-1100.00 Lakhs**

BOQ Item No	Description / Chainage		Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit/ Remarks	Rate	Amount
1	KSRRB 300-1. Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications(P.No-143 &136 ,I No-19.1&17.4& 17.1) 5km lead= 57+2.0x1.28x5=69.80												
	Kogilu Surrounding Area												
	Prakruthi Nagar												
	9th,10th,10th A link Road												
	LHS												
	0.00	15.00		1	15.00			0.60	0.40	3.60	0.9 pcs		
	15.00	28.00		1	13.00			0.60	0.40	3.12	0.9bs		
	28.00	35.00		0	7.00			0.60	0.40	0.00	9th cross Rd		
	35.00	48.70		1	13.70			0.60	0.40	3.29	0.9bs		
	48.70	61.50		1	12.80			0.60	0.40	3.07	0.9pcs		
	61.50	68.50		0	7.00			0.60	0.40	0.00	Cross Road		
	RHS												
	0.00	15.00		1	15.00			0.60	0.40	3.60	0.9pcs		
	15.00	28.00		1	13.00			0.60	0.40	3.12	0.9pcs		
	28.00	35.00		1	7.00			0.60	0.40	1.68	9th cross Rd		
	35.00	48.70		1	13.70			0.60	0.40	3.29	0.9pcs		
	48.70	64.20		1	15.50			0.60	0.40	3.72	0.9pcs		
	64.20	68.50		1	4.30			0.60	0.40	1.03	only desilt		
	9th Cross Road												
	LHS												
	0.00	9.30		1	9.30			0.60	0.40	2.23	1.2pcs		
	9.30	19.00		1	9.70			0.60	0.40	2.33	1.2bs		
	19.00	27.60		1	8.60			0.60	0.40	2.06	1.2bs		
	27.60	36.60		1	9.00			0.60	0.40	2.16	1.2bs		
	36.60	54.70		1	18.10			0.60	0.40	4.34	0.9pcs		
	54.70	64.00		1	9.30			0.60	0.40	2.23	only desilt		
	64.00	73.00		1	9.00			0.60	0.40	2.16	0.9pcs		
	73.00	91.70		1	18.70			0.60	0.40	4.49	1.2bs		
	91.70	110.70		1	19.00			0.60	0.40	4.56	0.9pcs		
	110.70	117.50		0	6.80			0.60	0.40	0.00	Link Road		
	117.50	128.00		1	10.50			0.60	0.40	2.52	0.9bs		
	128.00	137.50		1	9.50			0.60	0.40	2.28	0.9pcs		
	137.50	155.50		1	18.00			0.60	0.40	4.32	0.9pcs		
	155.50	173.50		1	18.00			0.60	0.40	4.32	1.2bs		
	173.50	192.00		1	18.50			0.60	0.40	4.44	0.9pcs		
	192.00	219.50		1	27.50			0.60	0.40	6.60	0.9bs		
	219.50	237.00		1	17.50			0.60	0.40	4.20	0.9pcs		
	237.00	248.00		1	11.00			0.60	0.40	2.64	only desilt		
	248.00	265.00		1	17.00			0.60	0.40	4.08	1.2bs		
	265.00	278.00		0	13.00			0.60	0.40	0.00	No work		
	RHS												
	0.00	19.00		0	19.00			0.60	0.40	0.00	no drain		
	19.00	36.60		1	17.60			0.60	0.40	4.22	0.9pcs		
	36.60	54.70		1	18.10			0.60	0.40	4.34	0.9pcs		
	54.70	73.00		1	18.30			0.60	0.40	4.39	0.9pcs		
	73.00	110.70		1	37.70			0.60	0.40	9.05	0.9pcs		
	110.70	117.50		0	6.80			0.60	0.40	0.00	Link road		
	117.50	137.50		1	20.00			0.60	0.40	4.80	0.9bs		
	137.50	192.00		1	54.50			0.60	0.40	13.08	0.9pcs		
	192.00	210.00		1	18.00			0.60	0.40	4.32	0.9bs		
	210.00	246.60		1	36.60			0.60	0.40	8.78	0.9bs		
	246.60	275.00		1	28.40			0.60	0.40	6.82	desilt		
	275.00	278.00		0	3.00			0.60	0.40	0.00	no drain		
	6th E Cross Road												
	LHS												
	0.00	3.50		1	3.50			0.60	0.40	0.84	only Desilt		
	3.50	22.00		1	18.50			0.60	0.40	4.44	0.9pcs		
	22.00	28.80		0	6.80			0.60	0.40	0.00	6th Cross Road		
	28.80	75.50		1	46.70			0.60	0.40	11.21	0.9bs		

BOQ Item No	Description Chainage		Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit/ Remarks	Rate	Amount
	75.50	89.00		1	13.50			0.60	0.40	3.24	only Desilt		
	89.00	93.00		0	4.00			0.60	0.40	0.00	No Drain		
	RHS												
	0.00	3.50		1	3.50			0.60	0.40	0.84	1.2bs		
	3.50	11.50		1	8.00			0.60	0.40	1.92	0.9pcs		
	11.50	22.00		1	10.50			0.60	0.40	2.52	0.9bs		
	22.00	28.80		0	6.80			0.60	0.40	0.00	6th Cross Road		
	28.80	57.30		1	28.50			0.60	0.40	6.84	0.9pcs		
	57.30	66.40		1	9.10			0.60	0.40	2.18	1.2bs		
	66.40	89.00		1	22.60			0.60	0.40	5.42	0.9pcs		
	89.00	93.00		0	4.00			0.60	0.40	0.00	No Drain		
	Cross Road B/W 6th E and 6th D												
	LHS												
	0.00	16.00		1	16.00			0.60	0.40	3.84	0.9pcs		
	16.00	28.00		1	12.00			0.60	0.40	2.88	0.9pcs		
	28.00	30.00		1	2.00			0.60	0.40	0.48	No Drain		
	RHS												
	0.00	16.00		1	16.00			0.60	0.40	3.84	0.9pcs		
	16.00	28.00		1	12.00			0.60	0.40	2.88	0.9bs		
	28.00	30.00		1	2.00			0.60	0.40	0.48	only Desilt		
	6th D Cross Road												
	LHS												
	0.00	19.50		1	19.50			0.60	0.40	4.68	0.9pcs		
	19.50	29.00		1	9.50			0.60	0.40	2.28	0.9pcs		
	29.00	46.50		1	17.50			0.60	0.40	4.20	0.9pcs		
	46.50	61.00		1	14.50			0.60	0.40	3.48	0.9bs		
	61.00	63.20		0	2.20			0.60	0.40	0.00	no drain		
	RHS												
	0.00	19.50		1	19.50			0.60	0.40	4.68	0.9pcs		
	19.50	29.00		1	9.50			0.60	0.40	2.28	1.2bs		
	29.00	46.50		1	17.50			0.60	0.40	4.20	0.9pcs		
	46.50	63.20		0	16.70			0.60	0.40	0.00	No drain		
	6th C Cross Road												
	LHS												
	0.00	10.40		1	10.40			0.60	0.40	2.50	only Desilt		
	10.40	14.40		1	4.00			0.60	0.40	0.96	0.9bs		
	14.40	29.50		0	15.10			0.60	0.40	0.00	No work		
	29.50	37.00		1	7.50			0.60	0.40	1.80	0.9bs		
	37.00	46.50		1	9.50			0.60	0.40	2.28	0.9pcs		
	46.50	65.80		1	19.30			0.60	0.40	4.63	0.9pcs		
	65.80	72.30		0	6.50			0.60	0.40	0.00	6th Cross Road		
	72.30	101.50		1	29.20			0.60	0.40	7.01	0.9pcs		
	101.50	106.50		1	5.00			0.60	0.40	1.20	only Desilt		
	RHS												
	0.00	10.40		1	10.40			0.60	0.40	2.50	only Desilt		
	10.40	14.40		0	4.00			0.60	0.40	0.00	No work		
	14.40	37.00		1	22.60			0.60	0.40	5.42	0.9bs		
	37.00	46.50		1	9.50			0.60	0.40	2.28	1.2bs		
	46.50	65.80		1	19.30			0.60	0.40	4.63	0.9pcs		
	65.80	72.30		0	6.50			0.60	0.40	0.00	6th Cross Road		
	72.30	99.50		1	27.20			0.60	0.40	6.53	0.9bs		
	99.50	106.50		0	7.00			0.60	0.40	0.00	No drain		
	Cross Road B/W 6th C and 6th B												
	LHS												
	0.00	4.00		1	4.00			0.60	0.40	0.96	1.2bs		
	4.00	8.70		1	4.70			0.60	0.40	1.13	0.9pcs		
	8.70	27.50		1	18.80			0.60	0.40	4.51	0.9pcs		
	27.50	33.70		0	6.20			0.60	0.40	0.00	Cross Road		
	33.70	47.00		1	13.30			0.60	0.40	3.19	0.9pcs		
	RHS												
	0.00	4.00		1	4.00			0.60	0.40	0.96	0.9pcs		
	4.00	8.70		1	4.70			0.60	0.40	1.13	.9bs		
	8.70	27.50		1	18.80			0.60	0.40	4.51	0.9pcs		
	27.50	33.70		0	6.20			0.60	0.40	0.00	Cross Road		
	33.70	45.00		1	11.30			0.60	0.40	2.71	0.9pcs		

BOQ Item No	Description Chainage		Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit/ Remarks	Rate	Amount
	6th A Cross Road												
	LHS												
	0.00	15.00		1	15.00			0.60	0.40	3.60	0.9pcs		
	15.00	31.00		1	16.00			0.60	0.40	3.84	0.9pcs		
	RHS												
	0.00	15.00		1	15.00			0.60	0.40	3.60	0.9pcs		
	15.00	31.00		1	16.00			0.60	0.40	3.84	0.9pcs		
	6th B Cross Road												
	LHS												
	0.00	10.50		1	10.50			0.60	0.40	2.52	Open Drain		
	10.50	15.70		1	5.20			0.60	0.40	1.25	Open Drain		
	15.70	30.00		1	14.30			0.60	0.40	3.43	0.9pcs		
	30.00	45.00		1	15.00			0.60	0.40	3.60	0.9pcs		
	45.00	65.40		1	20.40			0.60	0.40	4.90	0.9pcs		
	RHS												
	0.00	10.50		1	10.50			0.60	0.40	2.52	0.9pcs		
	10.50	18.00		1	7.50			0.60	0.40	1.80	Culvert Desilt		
	18.00	30.00		1	12.00			0.60	0.40	2.88	0.9pcs		
	30.00	45.00		1	15.00			0.60	0.40	3.60	0.9pcs		
	45.00	64.00		1	19.00			0.60	0.40	4.56	0.9pcs		
	64.00	65.40		1	1.40			0.60	0.40	0.34	Open Drain		
	6th Cross Prakruthi Nagara												
	LHS												
	0.00	15.00		1	15.00			0.45	0.40	2.70	Open Drain		
	15.00	30.00		1	15.00			0.45	0.40	2.70	Open Drain		
	30.00	45.00		1	15.00			0.45	0.40	2.70	Open Drain		
	45.00	60.80		1	15.80			0.45	0.40	2.84	Open Drain		
	60.80	85.00		1	24.20			0.45	0.40	4.36	Open drain		
	85.00	96.00		1	11.00			0.45	0.40	1.98	1m BS slab		
	96.00	102.40		1	6.40			0.45	0.40	1.15	Open drain		
	102.40	114.50		1	12.10			0.45	0.40	2.18	1.2m BS Slab		
	5th Cross Prakruthi Nagara												
	LHS												
	0.00	15.00		1	15.00			0.45	0.40	2.70	Open Drain		
	15.00	37.60		1	22.60			0.45	0.40	4.07	Open Drain		
	37.60	50.00		1	12.40			0.45	0.40	2.23	1.2m BS Slab		
	50.00	60.00		1	10.00			0.45	0.40	1.80	Open Drain		
	60.00	74.40		1	14.40			0.45	0.40	2.59	Open drain		
	74.40	90.00		1	15.60			0.45	0.40	2.81	Open drain		
	90.00	109.30		1	19.30			0.45	0.40	3.47	Open drain		
	RHS												
	0.00	15.00		1	15.00			0.45	0.40	2.70	Open Drain		
	15.00	37.60		1	22.60			0.45	0.40	4.07	Open Drain		
	37.60	60.00		1	22.40			0.45	0.40	4.03	Open Drain		
	60.00	74.40		1	14.40			0.45	0.40	2.59	0.9m BS slab		
	74.40	98.60		1	24.20			0.45	0.40	4.36	Open drain		
	98.60	109.30		1	10.70			0.45	0.40	1.93	0.9m BS slab		
	4th Cross Prakruthi Nagara												
	LHS												
	0.00	15.00		1	15.00			0.45	0.40	2.70	Open Drain		
	15.00	30.00		1	15.00			0.45	0.40	2.70	Open Drain		
	30.00	45.00		1	15.00			0.45	0.40	2.70	Open Drain		
	45.00	60.00		1	15.00			0.45	0.40	2.70	Open Drain		
	60.00	74.00		1	14.00			0.45	0.40	2.52	Open drain		
	74.00	86.20		1	12.20			0.45	0.40	2.20	0.9m BS slab		
	86.20	98.00		1	11.80			0.45	0.40	2.12	Open drain		
	98.00	110.30		1	12.30			0.45	0.40	2.21	0.9m BS slab		
	RHS												
	0.00	15.00		1	15.00			0.45	0.40	2.70	Open Drain		
	15.00	30.00		1	15.00			0.45	0.40	2.70	Open Drain		
	30.00	40.00		1	10.00			0.45	0.40	1.80	Open Drain		
	40.00	60.00		1	20.00			0.45	0.40	3.60	Open Drain		
	60.00	75.00		1	15.00			0.45	0.40	2.70	Open Drain		
	75.00	90.00		1	15.00			0.45	0.40	2.70	Open Drain		
	90.00	110.30		1	20.30			0.45	0.40	3.65	Open Drain		

BOQ Item No	Description Chainage		Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit/ Remarks	Rate	Amount
	3rd Cross Prakruthi Nagara(Sri Bhramhalingeshwara Juice and Condiments)												
	LHS												
	0.00	18.00		1	18.00			0.60	0.40	4.32	0.9 PCS		
	RHS												
	0.00	18.00		1	18.00			0.60	0.40	4.32	0.9m BS slab		
	1st Cross Prakruthi Nagara												
	LHS												
	0.00	11.00		1	11.00			0.60	0.40	2.64	0.9 PCS		
	11.00	31.70		1	20.70			0.60	0.40	4.97	Open Drain		
	31.70	45.00		1	13.30			0.60	0.40	3.19	0.9 PCS		
	45.00	60.00		1	15.00			0.60	0.40	3.60	0.9 PCS		
	60.00	73.30		1	13.30			0.60	0.40	3.19	0.9 PCS		
	RHS												
	0.00	15.00		1	15.00			0.60	0.40	3.60	0.9 PCS		
	15.00	30.00		1	15.00			0.60	0.40	3.60	0.9 PCS		
	30.00	40.00		1	10.00			0.60	0.40	2.40	0.9 PCS		
	40.00	60.00		1	20.00			0.60	0.40	4.80	0.9 PCS		
	60.00	73.30		1	13.30			0.60	0.40	3.19	0.9 PCS		
	Prakruthi Nagara Main Road												
	LHS												
	0.00	15.00		1	15.00			0.60	0.40	3.60	0.9 PCS		
	15.00	18.80		1	3.80			0.60	0.40	0.91	0.9 BS Slab		
	18.80	30.00		1	11.20			0.60	0.40	2.69	0.9 PCS		
	30.00	50.50		1	20.50			0.60	0.40	4.92	0.9 PCS		
	50.50	57.40		1	6.90			0.60	0.40	1.66	Culvert Desilt(1st C/s Rd)		
	57.40	60.00		1	2.60			0.60	0.40	0.62	0.9 PCS		
	60.00	75.00		1	15.00			0.60	0.40	3.60	0.9 PCS		
	75.00	90.00		1	15.00			0.60	0.40	3.60	0.9 PCS		
	90.00	108.60		1	18.60			0.60	0.40	4.46	0.9 PCS		
	108.60	115.00		1	6.40			0.60	0.40	1.54	Culvert Desilt(2nd C/s Rd)		
	115.00	130.00		1	15.00			0.60	0.40	3.60	0.9 PCS		
	130.00	145.00		1	15.00			0.60	0.40	3.60	0.9 PCS		
	145.00	154.00		1	9.00			0.60	0.40	2.16	0.9 PCS		
	154.00	161.00		1	7.00			0.60	0.40	1.68	Culvert Desilt(3rd C/s Rd)		
	161.00	180.00		1	19.00			0.60	0.40	4.56	0.9 PCS		
	180.00	195.00		1	15.00			0.60	0.40	3.60	0.9 PCS		
	195.00	210.00		1	15.00			0.60	0.40	3.60	0.9 PCS		
	210.00	216.50		1	6.50			0.60	0.40	1.56	Only Desilt(Deck Slab)		
	216.50	245.50		1	29.00			0.60	0.40	6.96	0.9 PCS		
	245.50	252.50		1	7.00			0.60	0.40	1.68	Culvert Desilt(5th C/s Rd)		
	252.50	291.30		1	38.80			0.60	0.40	9.31	0.9 PCS		
	291.30	298.00		1	6.70			0.60	0.40	1.61	Culvert Desilt(6th C/s Rd)		
	298.00	311.80		1	13.80			0.60	0.40	3.31	0.9m BS Slab		
	311.80	325.00		1	13.20			0.60	0.40	3.17	0.9 PCS		
	325.00	331.70		1	6.70			0.60	0.40	1.61	Culvert Desilt(7th C/s Rd)		
	331.70	358.40		1	26.70			0.60	0.40	6.41	0.9 PCS		
	358.40	367.30		0	8.90			0.60	0.40	0.00	8th Cross No Drain		
	RHS												
	0.00	15.00		1	15.00			0.60	0.40	3.60	0.9 PCS		
	15.00	18.80		1	3.80			0.60	0.40	0.91	0.9 PCS		
	18.80	30.00		1	11.20			0.60	0.40	2.69	0.9 PCS		
	30.00	50.60		1	20.60			0.60	0.40	4.94	0.9 PCS		
	50.60	58.00		1	7.40			0.60	0.40	1.78	Culvert Desilt(1st C/s Rd)		
	58.00	60.00		1	2.00			0.60	0.40	0.48	0.9 PCS		
	60.00	75.00		1	15.00			0.60	0.40	3.60	0.9 PCS		
	75.00	90.00		1	15.00			0.60	0.40	3.60	0.9 PCS		
	90.00	107.30		1	17.30			0.60	0.40	4.15	0.9 PCS		
	107.30	116.40		1	9.10			0.60	0.40	2.18	Culvert Desilt(2nd C/s Rd)		
	116.40	121.50		1	5.10			0.60	0.40	1.22	1.2m BS Slab		
	121.50	130.00		1	8.50			0.60	0.40	2.04	0.9 PCS		

BOQ Item No	Description Chainage		Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit/ Remarks	Rate	Amount
	130.00	154.20		1	24.20			0.60	0.40	5.81	0.9 PCS		
	154.20	162.00		1	7.80			0.60	0.40	1.87	Culvert Desilt(3rd C/s Rd)		
	162.00	180.00		1	18.00			0.60	0.40	4.32	0.9 PCS		
	180.00	199.80		1	19.80			0.60	0.40	4.75	0.9 PCS		
	199.80	207.00		1	7.20			0.60	0.40	1.73	Culvert Desilt(4th C/s Rd)		
	207.00	215.00		1	8.00			0.60	0.40	1.92	0.9 PCS		
	215.00	230.00		1	15.00			0.60	0.40	3.60	0.9 PCS		
	230.00	246.20		1	16.20			0.60	0.40	3.89	0.9 PCS		
	246.20	253.00		1	6.80			0.60	0.40	1.63	Culvert Desilt(5th C/s Rd)		
	253.00	275.00		1	22.00			0.60	0.40	5.28	0.9 PCS		
	275.00	292.00		1	17.00			0.60	0.40	4.08	0.9 PCS		
	292.00	298.80		1	6.80			0.60	0.40	1.63	Culvert Desilt(6th C/s Rd)		
	298.80	310.00		1	11.20			0.60	0.40	2.69	0.9 PCS		
	310.00	330.00		1	20.00			0.60	0.40	4.80	0.9 PCS		
	330.00	346.70		1	16.70			0.60	0.40	4.01	0.9 PCS		
	346.70	354.40		1	7.70			0.60	0.40	1.85	0.9 BS Slab		
	354.40	367.30		1	12.90			0.60	0.40	3.10	0.9 PCS		
	Tirumenahalli Main Road												
	LHS												
	0.00	15.00		1	15.00			0.60	0.40	3.60	Open drain		
	15.00	30.00		1	15.00			0.60	0.40	3.60	Open drain		
	30.00	45.00		1	15.00			0.60	0.40	3.60	Open drain		
	45.00	60.00		1	15.00			0.60	0.40	3.60	Open drain		
	60.00	75.00		1	15.00			0.60	0.40	3.60	Open drain		
	75.00	90.00		1	15.00			0.60	0.40	3.60	Open drain		
	90.00	108.00		1	18.00			0.60	0.40	4.32	Open drain		
	108.00	123.00		1	15.00			0.60	0.40	3.60	Open drain		
	123.00	138.00		1	15.00			0.60	0.40	3.60	Open drain		
	138.00	153.00		1	15.00			0.60	0.40	3.60	Open drain		
	153.00	168.00		1	15.00			0.60	0.40	3.60	Open drain		
	168.00	183.00		1	15.00			0.60	0.40	3.60	Open drain		
	183.00	198.00		1	15.00			0.60	0.40	3.60	Open drain		
	198.00	210.00		1	12.00			0.60	0.40	2.88	Open drain		
	210.00	225.00		1	15.00			0.60	0.40	3.60	Open drain		
	225.00	240.00		1	15.00			0.60	0.40	3.60	Open drain		
	240.00	255.00		1	15.00			0.60	0.40	3.60	Open drain		
	255.00	270.00		1	15.00			0.60	0.40	3.60	Open drain		
	270.00	285.00		1	15.00			0.60	0.40	3.60	Open drain		
	285.00	300.00		1	15.00			0.60	0.40	3.60	Open drain		
	300.00	315.00		1	15.00			0.60	0.40	3.60	Open drain		
	315.00	330.00		1	15.00			0.60	0.40	3.60	Open drain		
	330.00	345.00		1	15.00			0.60	0.40	3.60	Open drain		
	345.00	360.00		1	15.00			0.60	0.40	3.60	Open drain		
	360.00	375.00		1	15.00			0.60	0.40	3.60	Open drain		
	375.00	390.00		1	15.00			0.60	0.40	3.60	Open drain		
	390.00	405.00		1	15.00			0.60	0.40	3.60	Open drain		
	405.00	420.00		1	15.00			0.60	0.40	3.60	Open drain		
	420.00	435.00		1	15.00			0.60	0.40	3.60	Open drain		
	435.00	450.00		1	15.00			0.60	0.40	3.60	Open drain		
	450.00	465.00		1	15.00			0.60	0.40	3.60	Open drain		
	465.00	477.00		1	12.00			0.60	0.40	2.88	Open drain		
	477.00	492.00		1	15.00			0.60	0.40	3.60	Open drain		
	492.00	505.00		1	13.00			0.60	0.40	3.12	Open drain		
	RHS												
	0.00	21.30		1	21.30			0.60	0.40	5.11	0.9 PCS		
	21.30	27.70		1	6.40			0.60	0.40	1.54	Open drain		
	27.70	45.00		1	17.30			0.60	0.40	4.15	0.9 PCS		
	45.00	67.90		1	22.90			0.60	0.40	5.50	0.9 PCS		
	67.90	75.00		1	7.10			0.60	0.40	1.70	Open drain		
	75.00	90.00		1	15.00			0.60	0.40	3.60	Open drain		
	90.00	105.00		1	15.00			0.60	0.40	3.60	Open drain		
	105.00	120.00		1	15.00			0.60	0.40	3.60	Open drain		
	120.00	135.00		1	15.00			0.60	0.40	3.60	Open drain		
	135.00	150.00		1	15.00			0.60	0.40	3.60	Open drain		
	150.00	165.00		1	15.00			0.60	0.40	3.60	Open drain		
	165.00	180.00		1	15.00			0.60	0.40	3.60	Open drain		
	180.00	195.00		1	15.00			0.60	0.40	3.60	Open drain		
	195.00	210.00		1	15.00			0.60	0.40	3.60	Open drain		
	210.00	225.00		1	15.00			0.60	0.40	3.60	Open drain		

BOQ Item No	Description Chainage		Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit/ Remarks	Rate	Amount
	225.00	240.00		1	15.00			0.60	0.40	3.60	Open drain		
	240.00	255.00		1	15.00			0.60	0.40	3.60	Open drain		
	255.00	270.00		1	15.00			0.60	0.40	3.60	Open drain		
	270.00	280.00		1	10.00			0.60	0.40	2.40	Open drain		
	280.00	295.00		1	15.00			0.60	0.40	3.60	Open drain		
	295.00	310.00		1	15.00			0.60	0.40	3.60	Open drain		
	310.00	325.00		1	15.00			0.60	0.40	3.60	Open drain		
	325.00	340.00		1	15.00			0.60	0.40	3.60	Open drain		
	340.00	355.00		1	15.00			0.60	0.40	3.60	Open drain		
	355.00	370.00		1	15.00			0.60	0.40	3.60	Open drain		
	370.00	385.00		1	15.00			0.60	0.40	3.60	Open drain		
	385.00	400.00		1	15.00			0.60	0.40	3.60	Open drain		
	400.00	415.00		1	15.00			0.60	0.40	3.60	Open drain		
	415.00	430.00		1	15.00			0.60	0.40	3.60	Open drain		
	430.00	445.00		1	15.00			0.60	0.40	3.60	Open drain		
	445.00	460.00		1	15.00			0.60	0.40	3.60	Open drain		
	460.00	475.00		1	15.00			0.60	0.40	3.60	Open drain		
	475.00	490.00		1	15.00			0.60	0.40	3.60	Open drain		
	490.00	507.00		1	17.00			0.60	0.40	4.08	Open drain		
	Tirumenahalli Main Road												
	New SSM Culvert												
	752.40	754.50		1	11.40			1.85	0.84	17.72			
	Tirumenahalli Main Road(from Gov.t School)												
	New BS Drain												
	LHS												
	505.00	520.00		1	15.00			0.70	0.70	7.35			
	520.00	535.00		1	15.00			0.70	0.70	7.35			
	535.00	550.00		1	15.00			0.70	0.70	7.35			
	550.00	565.00		1	15.00			0.70	0.70	7.35			
	565.00	580.00		1	15.00			0.70	0.70	7.35			
	580.00	595.00		1	15.00			0.70	0.70	7.35			
	595.00	605.00		1	10.00			0.70	0.70	4.90			
	RHS												
	507.00	520.00		1	13.00			0.70	0.70	6.37			
	520.00	535.00		1	15.00			0.70	0.70	7.35			
	535.00	550.00		1	15.00			0.70	0.70	7.35			
	550.00	565.00		1	15.00			0.70	0.70	7.35			
	565.00	580.00		1	15.00			0.70	0.70	7.35			
	580.00	595.00		1	15.00			0.70	0.70	7.35			
	595.00	605.00		1	10.00			0.70	0.70	4.90			
	605.00	632.00		0	27.00					0.00	No work		
	632.00	640.00		1	8.00			0.70	0.70	3.92			
	640.00	655.00		1	15.00			0.70	0.70	7.35			
	655.00	670.00		1	15.00			0.70	0.70	7.35			
	670.00	685.00		1	15.00			0.70	0.70	7.35			
	685.00	700.00		1	15.00			0.70	0.70	7.35			
	700.00	715.00		1	15.00			0.70	0.70	7.35			
	715.00	730.00		1	15.00			0.70	0.70	7.35			
	730.00	745.00		1	15.00			0.70	0.70	7.35			
	745.00	760.00		1	15.00			0.70	0.70	7.35			
	760.00	775.00		1	15.00			0.70	0.70	7.35			
	775.00	790.00		1	15.00			0.70	0.70	7.35			
	790.00	805.00		1	15.00			0.70	0.70	7.35			
	805.00	820.00		1	15.00			0.70	0.70	7.35			
	820.00	835.00		1	15.00			0.70	0.70	7.35			
	835.00	850.00		1	15.00			0.70	0.70	7.35			
	850.00	865.00		1	15.00			0.70	0.70	7.35			
	865.00	880.00		1	15.00			0.70	0.70	7.35			
	880.00	895.00		1	15.00			0.70	0.70	7.35			
	895.00	910.00		1	15.00			0.70	0.70	7.35			
	910.00	925.00		1	15.00			0.70	0.70	7.35			
	925.00	940.00		1	15.00			0.70	0.70	7.35			
	940.00	955.00		1	15.00			0.70	0.70	7.35			
	955.00	970.00		1	15.00			0.70	0.70	7.35			
	970.00	985.00		1	15.00			0.70	0.70	7.35			
	985.00	1000.00		1	15.00			0.70	0.70	7.35			
	1000.00	1007.00		1	7.00			0.70	0.70	3.43			
	Kogilu Surrounding Area												
	New RCC Culvert												
	Thirumenahalli Mn Rd												
				1	9.10			2.60	1.80	42.59			

BOQ Item No	Description Chainage		Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit/ Remarks	Rate	Amount
	Agrahara Surrounding Area												
	MS Nagara 6th c/s Road												
	LHS												
	0.00	15.00		1	15.00			0.60	0.40	3.60	Open drain		
	15.00	32.50		1	17.50			0.60	0.40	4.20	Open drain		
	32.50	44.30		1	11.80			0.60	0.40	2.83	0.9 BS slab		
	44.30	60.00		1	15.70			0.60	0.40	3.77	Open drain		
	60.00	75.00		1	15.00			0.60	0.40	3.60	Open drain		
	75.00	90.00		1	15.00			0.60	0.40	3.60	Open drain		
	90.00	105.00		1	15.00			0.60	0.40	3.60	Open drain		
	105.00	120.00		1	15.00			0.60	0.40	3.60	Open drain		
	120.00	135.00		1	15.00			0.60	0.40	3.60	Open drain		
	135.00	147.30		1	12.30			0.60	0.40	2.95	Open drain		
	RHS												
	0.00	15.00		1	15.00			0.60	0.40	3.60	Open drain		
	15.00	30.00		1	15.00			0.60	0.40	3.60	Open drain		
	30.00	45.00		1	15.00			0.60	0.40	3.60	Open drain		
	45.00	60.00		1	15.00			0.60	0.40	3.60	Open drain		
	60.00	75.00		1	15.00			0.60	0.40	3.60	Open drain		
	75.00	90.00		1	15.00			0.60	0.40	3.60	Open drain		
	90.00	105.00		1	15.00			0.60	0.40	3.60	Open drain		
	105.00	120.00		1	15.00			0.60	0.40	3.60	Open drain		
	120.00	135.00		1	15.00			0.60	0.40	3.60	Open drain		
	135.00	153.50		1	18.50			0.60	0.40	4.44	Open drain		
	MS Nagara 7th c/s Road (W1145)												
	LHS												
	0.00	20.20		1	20.20			0.60	0.40	4.85	Open drain		
	20.20	44.40		1	24.20			0.60	0.40	5.81	0.9 BS slab		
	44.40	60.00		1	15.60			0.60	0.40	3.74	Open drain		
	60.00	75.00		1	15.00			0.60	0.40	3.60	Open drain		
	75.00	90.00		1	15.00			0.60	0.40	3.60	Open drain		
	90.00	105.00		1	15.00			0.60	0.40	3.60	Open drain		
	105.00	120.00		1	15.00			0.60	0.40	3.60	Open drain		
	120.00	137.30		1	17.30			0.60	0.40	4.15	Open drain		
	137.30	146.20		1	8.90			0.60	0.40	2.14	0.9 BS slab		
	146.20	151.20		0	5.00			0.60	0.40	0.00	No drain (c/s Road)		
	151.20	165.00		1	13.80			0.60	0.40	3.31	Open drain		
	165.00	180.00		1	15.00			0.60	0.40	3.60	Open drain		
	180.00	195.00		1	15.00			0.60	0.40	3.60	Open drain		
	195.00	210.00		1	15.00			0.60	0.40	3.60	Open drain		
	210.00	225.00		1	15.00			0.60	0.40	3.60	Open drain		
	225.00	234.70		1	9.70			0.60	0.40	2.33	Open drain		
	234.70	239.00		1	4.30			0.60	0.40	1.03	0.9 BS slab		
	239.00	248.70		1	9.70			0.60	0.40	2.33	Open drain		
	RHS												
	0.00	15.00		1	15.00			0.60	0.40	3.60	Open drain		
	15.00	30.00		1	15.00			0.60	0.40	3.60	Open drain		
	30.00	45.00		1	15.00			0.60	0.40	3.60	Open drain		
	45.00	60.00		1	15.00			0.60	0.40	3.60	Open drain		
	60.00	75.00		1	15.00			0.60	0.40	3.60	Open drain		
	75.00	90.00		1	15.00			0.60	0.40	3.60	Open drain		
	90.00	105.00		1	15.00			0.60	0.40	3.60	Open drain		
	105.00	120.00		1	15.00			0.60	0.40	3.60	Open drain		
	120.00	133.30		1	13.30			0.60	0.40	3.19	Open drain		
	133.30	146.20		1	12.90			0.60	0.40	3.10	1.2 BS slab		
	146.20	151.20		0	5.00			0.60	0.40	0.00	No drain (c/s Road)		
	151.20	182.70		1	31.50			0.60	0.40	7.56	Open drain		
	182.70	189.00		1	6.30			0.60	0.40	1.51	0.9 BS slab		
	189.00	195.00		1	6.00			0.60	0.40	1.44	1.2 BS slab		
	195.00	201.00		1	6.00			0.60	0.40	1.44	0.9 BS slab		
	201.00	248.70		1	47.70			0.60	0.40	11.45	Open drain		
	MS Nagara 8th c/s Road(W1139)												
	LHS												
	0.00	16.50		1	16.50			0.60	0.40	3.96	Open drain		
	16.50	25.80		1	9.30			0.60	0.40	2.23	0.9 PCS		
	25.80	52.70		1	26.90			0.60	0.40	6.46	Open drain		
	52.70	71.60		1	18.90			0.60	0.40	4.54	0.9 BS slab		
	71.60	90.00		1	18.40			0.60	0.40	4.42	Open drain		

BOQ Item No	Description Chainage		Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit/ Remarks	Rate	Amount
	90.00	105.00		1	15.00			0.60	0.40	3.60	Open drain		
	105.00	120.00		1	15.00			0.60	0.40	3.60	Open drain		
	120.00	135.00		1	15.00			0.60	0.40	3.60	Open drain		
	135.00	145.00		1	10.00			0.60	0.40	2.40	Open drain		
	145.00	151.00		0	6.00			0.60	0.40	0.00	No drain (c/s Road)		
	151.00	165.00		1	14.00			0.60	0.40	3.36	Open drain		
	165.00	180.00		1	15.00			0.60	0.40	3.60	Open drain		
	180.00	195.00		1	15.00			0.60	0.40	3.60	Open drain		
	195.00	210.00		1	15.00			0.60	0.40	3.60	Open drain		
	210.00	225.00		1	15.00			0.60	0.40	3.60	Open drain		
	225.00	240.00		1	15.00			0.60	0.40	3.60	Open drain		
	240.00	255.00		1	15.00			0.60	0.40	3.60	Open drain		
	255.00	270.00		1	15.00			0.60	0.40	3.60	Open drain		
	270.00	279.00		1	9.00			0.60	0.40	2.16	Open drain		
	RHS												
	0.00	5.40		1	5.40			0.60	0.40	1.30	Open drain		
	5.40	26.40		1	21.00			0.60	0.40	5.04	0.9 BS slab		
	26.40	30.00		1	3.60			0.60	0.40	0.86	Open drain		
	30.00	50.00		1	20.00			0.60	0.40	4.80	0.9 BS slab		
	50.00	53.00		1	3.00			0.60	0.40	0.72	Open drain		
	53.00	66.50		1	13.50			0.60	0.40	3.24	0.9 BS slab		
	66.50	75.00		1	8.50			0.60	0.40	2.04	Open drain		
	75.00	90.00		1	15.00			0.60	0.40	3.60	Open drain		
	90.00	105.00		1	15.00			0.60	0.40	3.60	Open drain		
	105.00	120.00		1	15.00			0.60	0.40	3.60	Open drain		
	120.00	135.00		1	15.00			0.60	0.40	3.60	Open drain		
	135.00	145.00		1	10.00			0.60	0.40	2.40	Open drain		
	145.00	151.00		0	6.00			0.60	0.40	0.00	No drain (c/s Road)		
	151.00	165.00		1	14.00			0.60	0.40	3.36	Open drain		
	165.00	180.00		1	15.00			0.60	0.40	3.60	Open drain		
	180.00	195.00		1	15.00			0.60	0.40	3.60	Open drain		
	195.00	210.00		1	15.00			0.60	0.40	3.60	Open drain		
	210.00	225.00		1	15.00			0.60	0.40	3.60	Open drain		
	225.00	240.00		1	15.00			0.60	0.40	3.60	Open drain		
	240.00	255.00		1	15.00			0.60	0.40	3.60	Open drain		
	255.00	270.00		1	15.00			0.60	0.40	3.60	Open drain		
	270.00	279.00		1	9.00			0.60	0.40	2.16	Open drain		
	MS Nagara 9th c/s Road(W1139A)												
	LHS												
	0.00	14.50		0	14.50			0.60	0.40	0.00	No drain		
	14.50	30.00		1	15.50			0.60	0.40	3.72	Open drain		
	30.00	45.00		1	15.00			0.60	0.40	3.60	Open drain		
	45.00	62.00		1	17.00			0.60	0.40	4.08	Open drain		
	62.00	71.00		1	9.00			0.60	0.40	2.16	0.9 BS slab		
	71.00	90.00		1	19.00			0.60	0.40	4.56	Open drain		
	90.00	109.00		1	19.00			0.60	0.40	4.56	Open drain		
	109.00	116.00		0	7.00			0.60	0.40	0.00	No work		
	116.00	144.00		1	28.00			0.60	0.40	6.72	Open drain		
	144.00	150.70		0	6.70			0.60	0.40	0.00	No work(2nd Mn rd)		
	150.70	164.00		1	13.30			0.60	0.40	3.19	0.9 BS slab		
	164.00	180.00		1	16.00			0.60	0.40	3.84	Open drain		
	180.00	195.00		1	15.00			0.60	0.40	3.60	Open drain		
	195.00	210.00		1	15.00			0.60	0.40	3.60	Open drain		
	210.00	225.00		1	15.00			0.60	0.40	3.60	Open drain		
	225.00	240.00		1	15.00			0.60	0.40	3.60	Open drain		
	240.00	255.00		1	15.00			0.60	0.40	3.60	Open drain		
	255.00	270.00		1	15.00			0.60	0.40	3.60	Open drain		
	270.00	279.50		1	9.50			0.60	0.40	2.28	Open drain		
	279.50	290.20		0	10.70			0.60	0.40	0.00	No work(3rd Mn rd)		
	290.20	300.00		1	9.80			0.60	0.40	2.35	Open drain		
	300.00	315.00		1	15.00			0.60	0.40	3.60	Open drain		
	315.00	330.00		1	15.00			0.60	0.40	3.60	Open drain		
	330.00	345.00		1	15.00			0.60	0.40	3.60	Open drain		
	345.00	360.00		1	15.00			0.60	0.40	3.60	Open drain		
	360.00	378.20		1	18.20			0.60	0.40	4.37	Open drain		
	RHS												
	0.00	11.30		1	11.30			0.60	0.40	2.71	1.2 BS slab		
	11.30	30.00		1	18.70			0.60	0.40	4.49	Open drain		

BOQ Item No	Description Chainage		Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit/ Remarks	Rate	Amount
	30.00	45.00		1	15.00			0.60	0.40	3.60	Open drain		
	45.00	66.00		1	21.00			0.60	0.40	5.04	Open drain		
	66.00	75.00		1	9.00			0.60	0.40	2.16	0.9 BS slab		
	75.00	93.00		1	18.00			0.60	0.40	4.32	Open drain		
	93.00	102.20		1	9.20			0.60	0.40	2.21	0.9 BS slab		
	102.20	121.00		1	18.80			0.60	0.40	4.51	Open drain		
	121.00	144.00		1	23.00			0.60	0.40	5.52	Open drain		
	144.00	150.70		0	6.70			0.60	0.40	0.00	No work(2nd Mn rd)		
	150.70	175.00		1	24.30			0.60	0.40	5.83	Open drain		
	175.00	183.00		1	8.00			0.60	0.40	1.92	Open drain		
	183.00	197.50		0	14.50			0.60	0.40	0.00	No work		
	197.50	200.00		1	2.50			0.60	0.40	0.60	Open drain		
	200.00	215.00		1	15.00			0.60	0.40	3.60	Open drain		
	215.00	230.00		1	15.00			0.60	0.40	3.60	Open drain		
	230.00	245.00		1	15.00			0.60	0.40	3.60	Open drain		
	245.00	260.00		1	15.00			0.60	0.40	3.60	Open drain		
	260.00	279.50		1	19.50			0.60	0.40	4.68	Open drain		
	279.50	290.20		1	10.70			0.60	0.40	2.57	No work(3rd Mn rd)		
	290.20	300.00		1	9.80			0.60	0.40	2.35	Open drain		
	300.00	315.00		1	15.00			0.60	0.40	3.60	Open drain		
	315.00	330.00		1	15.00			0.60	0.40	3.60	Open drain		
	330.00	345.00		1	15.00			0.60	0.40	3.60	Open drain		
	345.00	360.00		1	15.00			0.60	0.40	3.60	Open drain		
	360.00	378.20		1	18.20			0.60	0.40	4.37	Open drain		
	2nd Main Rd MS Nagara												
	LHS												
	0.00	6.60		0	6.60			0.60	0.40	0.00	No drain (6th c/s rd)		
	6.60	25.50		1	18.90			0.60	0.40	4.54	Open drain		
	25.50	39.00		1	13.50			0.60	0.40	3.24	1.2 BS slab		
	39.00	46.00		1	7.00			0.60	0.40	1.68	7th c/s Culvert Desilt (1.5 BS slab)		
	46.00	56.00		1	10.00			0.60	0.40	2.40	0.9 BS slab		
	56.00	76.50		1	20.50			0.60	0.40	4.92	Open drain		
	76.50	82.60		0	6.10			0.60	0.40	0.00	No work(8th c/s Rd)		
	82.60	100.00		1	17.40			0.60	0.40	4.18	Open drain		
	100.00	105.50		1	5.50			0.60	0.40	1.32	0.9 BS slab		
	105.50	108.60		1	3.10			0.60	0.40	0.74	Open drain		
	108.60	116.50		0	7.90			0.60	0.40	0.00	No work(9th c/s Rd)		
	116.50	150.40		1	33.90			0.60	0.40	8.14	Open drain		
	RHS												
	0.00	17.60		1	17.60			0.60	0.40	4.22	Open drain		
	17.60	22.90		0	5.30			0.60	0.40	0.00	Culvert(No work)		
	22.90	39.00		1	16.10			0.60	0.40	3.86	Open drain		
	39.00	47.00		0	8.00			0.60	0.40	0.00	7th c/s Culvert (No work)		
	47.00	72.80		1	25.80			0.60	0.40	6.19	Open drain		
	72.80	79.50		0	6.70			0.60	0.40	0.00	8th c/s Culvert (No work)		
	79.50	112.00		1	32.50			0.60	0.40	7.80	Open drain		
	112.00	119.40		0	7.40			0.60	0.40	0.00	9th c/s Culvert (No work)		
	119.40	133.00		1	13.60			0.60	0.40	3.26	0.9 BS slab		
	133.00	139.20		1	6.20			0.60	0.40	1.49	1.2 BS slab		
	139.20	150.40		1	11.20			0.60	0.40	2.69	Open drain		
	Connecting Rd to MS Nagara2nd Main Road												
	LHS												
	0.00	2.00		1	2.00			0.60	0.40	0.48	Open drain		
	2.00	19.20		1	17.20			0.60	0.40	4.13	0.9 BS slab		
	19.20	39.50		0	20.30			0.60	0.40	0.00	No drain		
	RHS												
	0.00	4.60		1	4.60			0.60	0.40	1.10	Open drain		
	4.60	13.00		0	8.40			0.60	0.40	0.00	No work		
	13.00	19.20		1	6.20			0.60	0.40	1.49	0.9 BS slab		
	19.20	22.20		1	3.00			0.60	0.40	0.72	Open drain		
	22.20	31.50		1	9.30			0.60	0.40	2.23	0.9 BS slab		
	31.50	39.50		0	8.00			0.60	0.40	0.00	No work		

BOQ Item No	Description Chainage		Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit/ Remarks	Rate	Amount
	3rd Main Rd MS Nagara												
	LHS												
	0.00	5.30		0	5.30			0.60	0.40	0.00	No Work (11th c/s rd)		
	5.30	18.00		1	12.70			0.60	0.40	3.05	Open drain		
	18.00	30.00		1	12.00			0.60	0.40	2.88	No work		
	30.00	45.00		1	15.00			0.60	0.40	3.60	No work		
	45.00	60.00		1	15.00			0.60	0.40	3.60	No work		
	60.00	68.20		1	8.20			0.60	0.40	1.97	No work		
	68.20	75.40		0	7.20			0.60	0.40	0.00	No work(9th c/s Rd)		
	75.40	90.00		1	14.60			0.60	0.40	3.50	Open drain		
	90.00	103.00		1	13.00			0.60	0.40	3.12	Open drain		
	103.00	111.30		1	8.30			0.60	0.40	1.99	0.9 BS slab		
	111.30	119.00		1	7.70			0.60	0.40	1.85	Open drain		
	119.00	128.50		1	9.50			0.60	0.40	2.28	1.2 BS slab		
	128.50	133.00		1	4.50			0.60	0.40	1.08	Open drain		
	133.00	138.00		1	5.00			0.60	0.40	1.20	0.9 BS slab		
	138.00	148.60		1	10.60			0.60	0.40	2.54	Open drain		
	148.60	156.50		1	7.90			0.60	0.40	1.90	No work(c/s Rd)		
	156.50	182.30		1	25.80			0.60	0.40	6.19	Open drain		
	182.30	189.80		0	7.50			0.60	0.40	0.00	No work(c/s Rd)		
	RHS												
	0.00	3.50		0	3.50			0.60	0.40	0.00	No work(11th c/s Rd)		
	3.50	13.50		1	10.00			0.60	0.40	2.40	Open drain		
	13.50	15.70		0	2.20			0.60	0.40	0.00	No work		
	15.70	29.00		1	13.30			0.60	0.40	3.19	0.9 BS slab		
	29.00	36.40		0	7.40			0.60	0.40	0.00	No work(10th c/s Rd)		
	36.40	49.40		0	13.00			0.60	0.40	0.00	No work		
	49.40	68.20		1	18.80			0.60	0.40	4.51	Open drain		
	68.20	76.20		0	8.00			0.60	0.40	0.00	9th c/s (No work)		
	76.20	108.20		1	32.00			0.60	0.40	7.68	Open drain		
	108.20	115.60		0	7.40			0.60	0.40	0.00	No work(8th c/s Rd)		
	115.60	133.00		1	17.40			0.60	0.40	4.18	Open drain		
	133.00	144.00		0	11.00			0.60	0.40	0.00	No work		
	144.00	150.00		1	6.00			0.60	0.40	1.44	Open drain		
	150.00	165.00		1	15.00			0.60	0.40	3.60	Open drain		
	165.00	180.00		1	15.00			0.60	0.40	3.60	Open drain		
	180.00	189.80		1	9.80			0.60	0.40	2.35	Open drain		
	Connecting Rd-1 to MS Nagara 3rd Main End Road												
	LHS												
	0.00	26.00		1	26.00			0.60	0.40	6.24	Open drain		
	26.00	30.00		1	4.00			0.60	0.40	0.96	Open drain		
	30.00	45.00		1	15.00			0.60	0.40	3.60	Open drain		
	45.00	60.00		1	15.00			0.60	0.40	3.60	Open drain		
	60.00	70.00		1	10.00			0.60	0.40	2.40	Open drain		
	70.00	79.10		1	9.10			0.60	0.40	2.18	0.9 BS slab		
	79.10	90.00		1	10.90			0.60	0.40	2.62	Open drain		
	90.00	105.00		1	15.00			0.60	0.40	3.60	Open drain		
	105.00	120.00		1	15.00			0.60	0.40	3.60	Open drain		
	120.00	130.00		1	10.00			0.60	0.40	2.40	Open drain		
	130.00	152.00		1	22.00			0.60	0.40	5.28	Open drain		
	152.00	161.00		1	9.00			0.60	0.40	2.16	0.9 BS slab		
	161.00	170.60		1	9.60			0.60	0.40	2.30	0.9 PCS slab		
	170.60	185.00		1	14.40			0.60	0.40	3.46	Open drain		
	185.00	200.00		1	15.00			0.60	0.40	3.60	Open drain		
	200.00	215.00		1	15.00			0.60	0.40	3.60	Open drain		
	215.00	230.00		1	15.00			0.60	0.40	3.60	Open drain		
	RHS												
	0.00	15.00		1	15.00			0.60	0.40	3.60	Open drain		
	15.00	30.00		1	15.00			0.60	0.40	3.60	Open drain		
	30.00	45.00		1	15.00			0.60	0.40	3.60	Open drain		
	45.00	60.00		1	15.00			0.60	0.40	3.60	Open drain		
	60.00	75.00		1	15.00			0.60	0.40	3.60	Open drain		
	75.00	85.80		1	10.80			0.60	0.40	2.59	Open drain		
	85.80	90.20		1	4.40			0.60	0.40	1.06	0.9 BS slab		
	90.20	94.50		1	4.30			0.60	0.40	1.03	1.2 BS slab		

BOQ Item No	Description		Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit/ Remarks	Rate	Amount
	Chainage												
	94.50	98.70		1	4.20			0.60	0.40	1.01	0.9 BS slab		
	98.70	103.40		1	4.70			0.60	0.40	1.13	1.2 BS slab		
	103.40	108.40		1	5.00			0.60	0.40	1.20	0.9 BS slab		
	108.40	112.40		1	4.00			0.60	0.40	0.96	1.2 BS slab		
	112.40	130.00		1	17.60			0.60	0.40	4.22	Open drain		
	130.00	145.00		1	15.00			0.60	0.40	3.60	Open drain		
	145.00	161.00		1	16.00			0.60	0.40	3.84	Open drain		
	161.00	167.00		1	6.00			0.60	0.40	1.44	Open drain		
	167.00	176.40		0	9.40			0.60	0.40	0.00	No work(home Entrance)		
	176.40	185.50		1	9.10			0.60	0.40	2.18	0.9 BS slab		
	185.50	204.00		1	18.50			0.60	0.40	4.44	Open drain		
	204.00	215.00		0	11.00			0.60	0.40	0.00	No work(home Entrance)		
	215.00	230.00		0	15.00			0.60	0.40	0.00	No work(home Entrance)		
	Connecting Rd-2 to MS Nagara 3rd Main Road												
	LHS												
	0.00	15.00		1	15.00			0.60	0.40	3.60	Open drain		
	15.00	30.00		1	15.00			0.60	0.40	3.60	Open drain		
	30.00	45.00		1	15.00			0.60	0.40	3.60	Open drain		
	45.00	60.00		1	15.00			0.60	0.40	3.60	Open drain		
	60.00	67.10		1	7.10			0.60	0.40	1.70	Open drain		
	67.10	71.90		1	4.80			0.60	0.40	1.15	0.9 BS slab		
	71.90	91.00		1	19.10			0.60	0.40	4.58	Open drain		
	91.00	94.40		1	3.40			0.60	0.40	0.82	0.9 BS slab		
	94.40	120.00		1	25.60			0.60	0.40	6.14	Open drain		
	120.00	135.00		1	15.00			0.60	0.40	3.60	Open drain		
	135.00	150.00		1	15.00			0.60	0.40	3.60	Open drain		
	150.00	165.00		1	15.00			0.60	0.40	3.60	Open drain		
	165.00	176.30		1	11.30			0.60	0.40	2.71	Open drain		
	176.30	190.00		1	13.70			0.60	0.40	3.29	0.9 BS slab		
	190.00	201.60		1	11.60			0.60	0.40	2.78	0.9 BS slab		
	201.60	227.80		1	26.20			0.60	0.40	6.29	Open drain		
	RHS												
	0.00	15.00		1	15.00			0.60	0.40	3.60	Open drain		
	15.00	30.00		1	15.00			0.60	0.40	3.60	Open drain		
	30.00	45.00		1	15.00			0.60	0.40	3.60	Open drain		
	45.00	60.00		1	15.00			0.60	0.40	3.60	Open drain		
	60.00	75.00		1	15.00			0.60	0.40	3.60	Open drain		
	75.00	90.00		1	15.00			0.60	0.40	3.60	Open drain		
	90.00	107.10		1	17.10			0.60	0.40	4.10	Open drain		
	107.10	111.40		1	4.30			0.60	0.40	1.03	1.2 PCS		
	111.40	121.60		1	10.20			0.60	0.40	2.45	Open drain		
	121.60	130.00		1	8.40			0.60	0.40	2.02	0.9 BS slab		
	130.00	149.00		1	19.00			0.60	0.40	4.56	0.9 BS slab		
	149.00	160.00		1	11.00			0.60	0.40	2.64	Open drain		
	160.00	176.30		1	16.30			0.60	0.40	3.91	Open drain		
	176.30	185.50		1	9.20			0.60	0.40	2.21	1.2 BS slab		
	185.50	200.00		1	14.50			0.60	0.40	3.48	Open drain		
	200.00	215.00		1	15.00			0.60	0.40	3.60	Open drain		
	215.00	227.80		1	12.80			0.60	0.40	3.07	Open drain		
	1st Block 5th street Tirumenahalli Road												
	LHS												
	0.00	15.00		1	15.00			0.60	0.40	3.60	0.9 PCS		
	15.00	31.00		1	16.00			0.60	0.40	3.84	0.9 PCS		
	3rd Block 5th c/s												
	RHS												
	0.00	15.00		1	15.00			0.60	0.40	3.60	0.9 PCS		
	15.00	30.00		1	15.00			0.60	0.40	3.60	0.9 PCS		
	30.00	45.00		1	15.00			0.60	0.40	3.60	0.9 PCS		
	45.00	49.00		1	4.00			0.60	0.40	0.96	0.9 PCS		
	49.00	60.00		0	11.00			0.60	0.40	0.00	No work(Home Entrance)		
	60.00	72.00		0	12.00			0.60	0.40	0.00	No work(Home Entrance)		
	3rd Block 6th c/s												
	RHS												
	0.00	15.00		1	15.00			0.60	0.40	3.60	Open drain		

BOQ Item No	Description Chainage		Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit/ Remarks	Rate	Amount
	15.00	30.00		1	15.00			0.60	0.40	3.60	Open drain		
	30.00	45.00		1	15.00			0.60	0.40	3.60	Open drain		
	45.00	49.00		1	4.00			0.60	0.40	0.96	Open drain		
	49.00	60.00		1	11.00			0.60	0.40	2.64	Open drain		
	60.00	76.40		1	16.40			0.60	0.40	3.94	Open drain		
	Agrahara Layout Main Road												
	GK Road to Agrahara Main Rd												
	LHS												
	0.00	15.00		1	15.00			0.80	0.80	9.60	1.5 PCS		
	15.00	36.30		1	21.30			0.80	0.80	13.63	1.5 PCS		
	36.30	45.00		1	8.70			0.80	0.80	5.57	Deck Slab		
	45.00	60.00		1	15.00			0.80	0.80	9.60	1.5 PCS		
	60.00	75.00		1	15.00			0.80	0.80	9.60	1.5 PCS		
	75.00	82.50		1	7.50			0.80	0.80	4.80	1.5 PCS		
	82.50	91.20		1	8.70			0.80	0.80	5.57	1.5 PCS		
	91.20	105.00		1	13.80			0.80	0.80	8.83	1.5 PCS		
	105.00	120.00		1	15.00			0.80	0.80	9.60	1.5 PCS		
	120.00	130.50		1	10.50			0.80	0.80	6.72	1.5 PCS		
	130.50	137.60		1	7.10			0.80	0.80	4.54	Culvert (BS Slab 1.6)		
	137.60	150.00		1	12.40			0.80	0.80	7.94	1.5 PCS		
	150.00	165.00		1	15.00			0.80	0.80	9.60	1.5 PCS		
	165.00	176.60		1	11.60			0.80	0.80	7.42	1.5 PCS		
	176.60	184.50		0	7.90			0.80	0.80	0.00	Cross Rd (Deck Slab)		
	184.50	195.00		1	10.50			0.80	0.80	6.72	1.5 PCS		
	195.00	210.00		1	15.00			0.80	0.80	9.60	1.5 PCS		
	210.00	222.60		1	12.60			0.80	0.80	8.06	1.5 PCS		
	222.60	230.50		1	7.90			0.80	0.80	5.06	Cross Rd (1.5 PCS)		
	230.50	241.00		1	10.50			0.80	0.80	6.72	1.5 PCS		
	241.00	248.00		1	7.00			0.80	0.80	4.48	0.9 BS Slab		
	248.00	253.50		0	5.50			0.80	0.80	0.00	Temple Entrance(No Work)		
	253.50	271.00		1	17.50			0.80	0.80	11.20	1.5 PCS		
	271.00	281.00		0	10.00			0.80	0.80	0.00	Cross Rd(No Work)		
	281.00	308.50		1	27.50			0.80	0.80	17.60	1.5 PCS		
	308.50	314.50		1	6.00			0.80	0.80	3.84	Deck Slab(No Work)		
	314.50	321.20		1	6.70			0.80	0.80	4.29	1.5 PCS		
	321.20	329.50		0	8.30			0.80	0.80	0.00	Cross Rd(No Work)		
	329.50	345.00		1	15.50			0.80	0.80	9.92	1.5 PCS		
	345.00	361.50		1	16.50			0.80	0.80	10.56	1.5 PCS		
	361.50	368.00		0	6.50			0.80	0.80	0.00	Cross Rd (Culvert 1.5PCS)		
	368.00	380.00		1	12.00			0.80	0.80	7.68	1.5 PCS		
	380.00	395.00		1	15.00			0.80	0.80	9.60	1.5 PCS		
	395.00	409.00		1	14.00			0.80	0.80	8.96	1.5 PCS		
	409.00	418.00		1	9.00			0.80	0.80	5.76	Cross Rd (Culvert 1.5PCS)		
	418.00	430.00		1	12.00			0.80	0.80	7.68	1.5 PCS		
	430.00	439.00		1	9.00			0.80	0.80	5.76	1.5 PCS		
	439.00	448.40		1	9.40			0.80	0.80	6.02	Culvert (BS Slab 1.5)		
	448.40	460.00		1	11.60			0.80	0.80	7.42	1.5 PCS		
	460.00	475.00		1	15.00			0.80	0.80	9.60	1.5 PCS		
	475.00	490.00		1	15.00			0.80	0.80	9.60	1.5 PCS		
	490.00	497.70		1	7.70			0.80	0.80	4.93	1.5 PCS		
	497.70	508.40		1	10.70			0.80	0.80	6.85	Cross Rd (Culvert 1.5PCS)		
	508.40	522.00		1	13.60			0.80	0.80	8.70	1.5 PCS		
	522.00	530.00		1	8.00			0.80	0.80	5.12	Open Drain		
	530.00	545.20		1	15.20			0.80	0.80	9.73	Open Drain		
	545.20	553.00		1	7.80			0.80	0.80	4.99	Cross Road(Only Desilt)		
	553.00	569.20		1	16.20			0.80	0.80	10.37	Open Drain		
	569.20	587.00		1	17.80			0.80	0.80	11.39	1.5 PCS		
	587.00	595.50		1	8.50			0.80	0.80	5.44	Cross Rd(Deck Slab)		

BOQ Item No	Description Chainage		Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit/ Remarks	Rate	Amount
	RHS												
	0.00	15.00		1	15.00			0.80	0.80	9.60	1.5 PCS		
	15.00	30.00		1	15.00			0.80	0.80	9.60	1.5 PCS		
	30.00	36.50		1	6.50			0.80	0.80	4.16	1.5 PCS		
	36.50	52.60		1	16.10			0.80	0.80	10.30	1.5 PCS		
	52.60	59.50		1	6.90			0.80	0.80	4.42	Deck Slab (Arogya Kendra)		
	59.50	82.50		1	23.00			0.80	0.80	14.72	1.5 PCS		
	82.50	91.20		0	8.70			0.80	0.80	0.00	Deck Slab(No works)		
	91.20	105.00		1	13.80			0.80	0.80	8.83	1.5 PCS		
	105.00	120.00		1	15.00			0.80	0.80	9.60	1.5 PCS		
	120.00	131.60		1	11.60			0.80	0.80	7.42	1.5 PCS		
	131.60	141.20		1	9.60			0.80	0.80	6.14	Cross Rd (1.5 PCS)		
	141.20	150.00		1	8.80			0.80	0.80	5.63	1.5 PCS		
	150.00	165.00		1	15.00			0.80	0.80	9.60	1.5 PCS		
	165.00	176.60		1	11.60			0.80	0.80	7.42	1.5 PCS		
	176.60	185.40		1	8.80			0.80	0.80	5.63	Culvert (1.5 PCS)		
	185.40	190.00		1	4.60			0.80	0.80	2.94	1.5 PCS		
	190.00	205.00		1	15.00			0.80	0.80	9.60	1.5 PCS		
	205.00	222.60		1	17.60			0.80	0.80	11.26	1.5 PCS		
	222.60	227.50		0	4.90			0.80	0.80	0.00	Cross Rd (No Work)		
	227.50	248.00		1	20.50			0.80	0.80	13.12	1.5 PCS		
	248.00	253.00		1	5.00			0.80	0.80	3.20	0.9 BS Slab		
	253.00	263.00		1	10.00			0.80	0.80	6.40	1.5 PCS		
	263.00	271.00		1	8.00			0.80	0.80	5.12	Cross Rd Culvert(1.5PCS)		
	271.00	293.50		1	22.50			0.80	0.80	14.40	1.5 PCS		
	293.50	299.00		1	5.50			0.80	0.80	3.52	Cross Rd (Deck Slab)		
	299.00	320.00		1	21.00			0.80	0.80	13.44	1.5 PCS		
	320.00	329.50		1	9.50			0.80	0.80	6.08	Cross Rd (Deck Slab)		
	329.50	335.00		1	5.50			0.80	0.80	3.52	1.5 PCS		
	335.00	350.00		1	15.00			0.80	0.80	9.60	1.5 PCS		
	350.00	365.00		1	15.00			0.80	0.80	9.60	1.5 PCS		
	365.00	371.00		1	6.00			0.80	0.80	3.84	1.5 PCS		
	371.00	379.00		1	8.00			0.80	0.80	5.12	Cross Rd (Deck Slab)		
	379.00	390.00		1	11.00			0.80	0.80	7.04	1.5 PCS		
	390.00	405.00		1	15.00			0.80	0.80	9.60	1.5 PCS		
	405.00	422.50		1	17.50			0.80	0.80	11.20	1.5 PCS		
	422.50	430.00		1	7.50			0.80	0.80	4.80	Cross Rd (1.5 PCS)		
	430.00	445.00		1	15.00			0.80	0.80	9.60	1.5 PCS		
	445.00	460.00		1	15.00			0.80	0.80	9.60	1.5 PCS		
	460.00	479.00		1	19.00			0.80	0.80	12.16	1.5 PCS		
	479.00	491.00		0	12.00			0.80	0.80	0.00	Cross Rd (No Work)		
	491.00	509.00		1	18.00			0.80	0.80	11.52	1.5 PCS		
	509.00	517.00		1	8.00			0.80	0.80	5.12	Cross Rd (Deck Slab)		
	517.00	530.00		1	13.00			0.80	0.80	8.32	1.5 PCS		
	530.00	545.00		1	15.00			0.80	0.80	9.60	1.5 PCS		
	545.00	558.00		1	13.00			0.80	0.80	8.32	1.5 PCS		
	558.00	568.70		1	10.70			0.80	0.80	6.85	Cross Rd (Deck Slab)		
	568.70	595.80		1	27.10			0.80	0.80	17.34	1.5 PCS		
	595.80	600.00		1	4.20			0.55	0.60	1.39	Open drain		
	600.00	615.00		1	15.00			0.55	0.60	4.95	Open drain		
	615.00	630.00		1	15.00			0.55	0.60	4.95	Open drain		
	630.00	642.50		1	12.50			0.55	0.60	4.13	0.50		
	642.50	651.60		0	9.10			0.55	0.60	0.00	No Work		
	651.60	660.50		1	8.90			0.50	0.40	1.78	Cross Rd (Culvert BS Slab)		
	660.50	671.00		1	10.50			0.50	0.40	2.10	Open drain		
	Balaji badavane												
	LHS												
	0.00	19.00		0	19.00			0.50	0.40	0.00	No work		
	19.00	46.00		1	27.00			0.50	0.40	5.40	Open drain		

BOQ Item No	Description Chainage		Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit/ Remarks	Rate	Amount
	RHS												
	0.00	30.00		1	30.00			0.50	0.40	6.00	Open drain		
	30.00	46.00		1	16.00			0.50	0.40	3.20	Open drain		
	Connected 4th A to 4th B												
	LHS												
	0.00	19.60		0	19.60			0.50	0.40	0.00	No work		
	19.60	33.00		1	13.40			0.50	0.40	2.68	Open drain		
	33.00	37.60		0	4.60			0.50	0.40	0.00	No work		
	RHS												
	0.00	32.00		0	32.00			0.50	0.40	0.00	No work		
	32.00	37.60		1	5.60			0.50	0.40	1.12	Open drain		
	4th A in Balajai Badavane												
	LHS												
	0.00	30.00		1	30.00			0.50	0.40	6.00	Open drain		
	30.00	60.00		1	30.00			0.50	0.40	6.00	Open drain		
	60.00	90.00		1	30.00			0.50	0.40	6.00	Open drain		
	90.00	112.00		1	22.00			0.50	0.40	4.40	Open drain		
	RHS												
	0.00	30.00		1	30.00			0.50	0.40	6.00	Open drain		
	30.00	60.00		1	30.00			0.50	0.40	6.00	Open drain		
	60.00	90.00		1	30.00			0.50	0.40	6.00	Open drain		
	90.00	110.50		1	20.50			0.50	0.40	4.10	Open drain		
	110.50	112.00		0	1.50			0.50	0.40	0.00	No work		
	4th B in Balajai Badavane												
	LHS												
	0.00	7.00		0	7.00			0.50	0.40	0.00	No work		
	7.00	37.00		1	30.00			0.50	0.40	6.00	Open drain		
	37.00	67.00		1	30.00			0.50	0.40	6.00	Open drain		
	67.00	97.00		1	30.00			0.50	0.40	6.00	Open drain		
	97.00	121.20		1	24.20			0.50	0.40	4.84	Open drain		
	RHS												
	0.00	7.00		1	7.00			0.50	0.40	1.40	Open drain		
	7.00	37.00		1	30.00			0.50	0.40	6.00	Open drain		
	37.00	67.00		1	30.00			0.50	0.40	6.00	Open drain		
	67.00	97.00		1	30.00			0.50	0.40	6.00	Open drain		
	97.00	121.20		1	24.20			0.50	0.40	4.84	Open drain		
	2nd Main Rd Kuvempu layout												
	Agrahara Layout Mn rd to manjunatha Mn Rd												
	LHS												
	0.00	30.00		1	30.00			0.50	0.40	6.00	Open drain		
	30.00	60.00		1	30.00			0.50	0.40	6.00	Open drain		
	60.00	79.20		1	19.20			0.50	0.40	3.84	Open drain		
	79.20	88.10		1	8.90			0.50	0.40	1.78	1.2 Bs		
	88.10	118.10		1	30.00			0.50	0.40	6.00	Open drain		
	118.10	147.50		1	29.40			0.50	0.40	5.88	Open drain		
	147.50	154.70		0	7.20			0.50	0.40	0.00	No work		
	154.70	186.60		1	31.90			0.50	0.40	6.38	Open drain		
	186.60	205.30		0	18.70			0.50	0.40	0.00	No work		
	205.30	229.00		1	23.70			0.50	0.40	4.74	Open drain		
	229.00	238.40		1	9.40			0.50	0.40	1.88	.9 Bs		
	238.40	268.40		1	30.00			0.50	0.40	6.00	Open drain		
	268.40	286.50		1	18.10			0.50	0.40	3.62	Open drain		
	RHS												
	0.00	30.00		1	30.00			0.50	0.40	6.00	Open drain		
	30.00	60.00		1	30.00			0.50	0.40	6.00	Open drain		
	60.00	90.00		1	30.00			0.50	0.40	6.00	Open drain		
	90.00	120.00		1	30.00			0.50	0.40	6.00	Open drain		
	120.00	125.40		1	5.40			0.50	0.40	1.08	Open drain		
	125.40	134.70		0	9.30			0.50	0.40	0.00	No work		
	134.70	147.50		1	12.80			0.50	0.40	2.56	Open drain		
	147.50	154.70		0	7.20			0.50	0.40	0.00	No work		
	154.70	168.60		1	13.90			0.50	0.40	2.78	Open drain		
	168.60	177.40		1	8.80			0.50	0.40	1.76	Open drain		
	177.40	185.60		1	8.20			0.50	0.40	1.64	Open drain		
	185.60	201.00		1	15.40			0.50	0.40	3.08	Open drain		
	201.00	231.00		1	30.00			0.50	0.40	6.00	Open drain		
	231.00	261.00		1	30.00			0.50	0.40	6.00	Open drain		
	261.00	267.00		1	6.00			0.50	0.40	1.20	Open drain		
	267.00	286.50		0	19.50			0.50	0.40	0.00	No work		

BOQ Item No	Description		Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit/ Remarks	Rate	Amount
	Chainage												
	Kuvempu Badavane Mn Rd												
	Agrahara Mn rd to 3rd Main Kuvempu Layout												
	LHS												
	0.00	2.80		0	2.80			0.50	0.40	0.00	No work		
	2.80	30.00		1	27.20			0.50	0.40	5.44	Open drain		
	30.00	36.00		0	6.00			0.50	0.40	0.00	No work		
	36.00	49.00		1	13.00			0.50	0.40	2.60	Open drain		
	49.00	56.70		0	7.70			0.50	0.40	0.00	No work		
	56.70	86.50		1	29.80			0.50	0.40	5.96	Open drain		
	86.50	93.50		0	7.00			0.50	0.40	0.00	No work		
	93.50	120.20		1	26.70			0.50	0.40	5.34	Open drain		
	RHS												
	0.00	2.80		0	2.80			0.50	0.40	0.00	No work		
	2.80	32.80		1	30.00			0.50	0.40	6.00	Open drain		
	32.80	45.00		0	12.20			0.50	0.40	0.00	No work		
	45.00	63.30		1	18.30			0.50	0.40	3.66	Open drain		
	63.30	86.50		1	23.20			0.50	0.40	4.64	Open drain		
	86.50	95.50		0	9.00			0.50	0.40	0.00	No work		
	95.50	120.20		1	24.70			0.50	0.40	4.94	Open drain		
	Manjunatha Layout rd												
	Agrahara Mn rd to 3rd Cross Manjunatha Layout												
	LHS												
	0.00	3.60		0	3.60			0.50	0.40	0.00	No work		
	3.60	30.50		1	26.90			0.50	0.40	5.38	Open drain		
	30.50	38.20		0	7.70			0.50	0.40	0.00	No work 1st Cs rd		
	38.20	64.40		1	26.20			0.50	0.40	5.24	Open drain		
	64.40	71.00		0	6.60			0.50	0.40	0.00	No work Cs rd		
	71.00	83.80		1	12.80			0.50	0.40	2.56	Open drain		
	83.80	97.50		1	13.70			0.50	0.40	2.74	Desilt		
	97.50	104.40		0	6.90			0.50	0.40	0.00	Cross Rd		
	104.40	122.00		0	17.60			0.50	0.40	0.00	No work		
	RHS												
	0.00	3.60		0	3.60			0.50	0.40	0.00	No work		
	3.60	31.60		1	28.00			0.50	0.40	5.60	Open drain		
	31.60	39.00		0	7.40			0.50	0.40	0.00	No work 1st Cs rd		
	39.00	64.40		1	25.40			0.50	0.40	5.08	Open drain		
	64.40	71.50		0	7.10			0.50	0.40	0.00	No work Cs rd		
	71.50	97.50		1	26.00			0.50	0.40	5.20	Open drain		
	97.50	104.40		0	6.90			0.50	0.40	0.00	Cross Rd		
	104.40	122.00		1	17.60			0.50	0.40	3.52	1.2Bs		
	Balajikrupa Main Road												
	11th cross (Masjidi to Arch)												
	LHS												
	0.00	26.00		1	26.00			0.50	0.50	6.50	0.9 PCS		
	26.00	34.00		0	8.00			0.50	0.50	0.00	10th cross Rd		
	34.00	40.00		1	6.00			0.50	0.50	1.50	0.9 PCS		
	40.00	46.00		0	6.00			0.50	0.50	0.00	1.2 BS Slab (Shop)		
	46.00	50.00		1	4.00			0.50	0.50	1.00	0.9 PCS		
	50.00	58.00		0	8.00			0.50	0.50	0.00	1.2 BS Slab (No Work)		
	58.00	60.00		1	2.00			0.50	0.50	0.50	0.9 PCS		
	60.00	64.00		0	4.00			0.50	0.50	0.00	9th cross Rd(No Work)		
	64.00	72.50		1	8.50			0.50	0.50	2.13	0.9 PCS		
	72.50	77.50		1	5.00			0.50	0.50	1.25	Deck Slab		
	77.50	81.00		0	3.50			0.50	0.50	0.00	8th cross Rd(No Work)		
	81.00	95.00		1	14.00			0.50	0.50	3.50	0.9 BS Slab		
	95.00	109.50		1	14.50			0.50	0.50	3.63	0.9 PCS		
	109.50	116.70		0	7.20			0.50	0.50	0.00	7th cross Rd(No Work)		
	116.70	139.50		1	22.80			0.50	0.50	5.70	0.9 PCS		
	139.50	147.00		0	7.50			0.50	0.50	0.00	6th cross Rd(No Work)		
	147.00	169.00		1	22.00			0.50	0.50	5.50	0.9 PCS		
	169.00	177.00		0	8.00			0.50	0.50	0.00	5th cross Rd(No Work)		
	177.00	209.00		1	32.00			0.50	0.50	8.00	Open Drain		
	209.00	215.80		0	6.80			0.50	0.50	0.00	4th cross Rd(No Work)		
	215.80	228.50		0	12.70			0.50	0.50	0.00	Deck Slab		
	228.50	236.00		1	7.50			0.50	0.50	1.88	0.9 PCS		
	236.00	241.80		1	5.80			0.50	0.50	1.45	0.9 BS Slab		
	241.80	248.10		0	6.30			0.50	0.50	0.00	3rd cross Rd(No Work)		

BOQ Item No	Description Chainage		Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit/ Remarks	Rate	Amount
	248.10	274.00		1	25.90			0.50	0.50	6.48	Open Drain		
	274.00	280.60		0	6.60			0.50	0.50	0.00	2nd cross Rd(No Work)		
	280.60	306.50		1	25.90			0.50	0.50	6.47	Open Drain		
	306.50	313.00		0	6.50			0.50	0.50	0.00	1st cross Rd(No Work)		
	313.00	332.00		0	19.00			0.50	0.50	0.00	No Work		
	RHS												
	0.00	13.80		0	13.80			0.50	0.50	0.00	Masjid (No Work)		
	13.80	26.00		0	12.20			0.50	0.50	0.00	No Work		
	26.00	34.00		0	8.00			0.50	0.50	0.00	10th cross Rd(No Work)		
	34.00	50.00		0	16.00			0.50	0.50	0.00	No Work		
	50.00	62.00		1	12.00			0.50	0.50	3.00	0.9 PCS		
	62.00	70.00		0	8.00			0.50	0.50	0.00	9th cross Rd(No Work)		
	70.00	83.00		0	13.00			0.50	0.50	0.00	Deck Slab		
	83.00	98.00		1	15.00			0.50	0.50	3.75	0.9 PCS		
	98.00	102.00		1	4.00			0.50	0.50	1.00	1.2 BS Slab		
	102.00	109.50		0	7.50			0.50	0.50	0.00	7th cross Rd(No Work)		
	109.50	139.50		1	30.00			0.50	0.50	7.50	Open Drain		
	139.50	147.00		1	7.50			0.50	0.50	1.88	6th cross Rd(No Work)		
	147.00	157.00		0	10.00			0.50	0.50	0.00	No Work		
	157.00	169.00		1	12.00			0.50	0.50	3.00	Open Drain		
	169.00	177.00		0	8.00			0.50	0.50	0.00	5th cross Rd(No Work)		
	177.00	209.00		1	32.00			0.50	0.50	8.00	Open Drain		
	209.00	215.80		0	6.80			0.50	0.50	0.00	4th cross Rd(No Work)		
	215.80	241.80		1	26.00			0.50	0.50	6.50	Open Drain		
	241.80	248.10		0	6.30			0.50	0.50	0.00	3rd cross Rd(No Work)		
	248.10	274.00		1	25.90			0.50	0.50	6.48	Open Drain		
	274.00	280.60		0	6.60			0.50	0.50	0.00	2nd cross Rd(No Work)		
	280.60	293.50		1	12.90			0.50	0.50	3.22	0.9 BS Sab		
	293.50	306.50		1	13.00			0.50	0.50	3.25	Open Drain		
	306.50	313.00		0	6.50			0.50	0.50	0.00	1st cross Rd(No Work)		
	313.00	331.00		1	18.00			0.50	0.50	4.50			
	1st Cross Road												
	LHS												
	0.00	15.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	15.00	30.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	30.00	45.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	45.00	60.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	60.00	75.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	75.00	92.00		1	17.00			0.50	0.40	3.40	Only Desilt		
	92.00	102.80		0	10.80			0.50	0.40	0.00	Balajikrupa Main Road		
	102.80	105.00		1	2.20			0.50	0.40	0.44	Only Desilt		
	105.00	120.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	120.00	135.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	135.00	150.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	150.00	165.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	165.00	180.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	180.00	195.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	195.00	210.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	210.00	225.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	225.00	240.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	240.00	250.70		1	10.70			0.50	0.40	2.14	Only Desilt		
	RHS												
	0.00	15.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	15.00	30.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	30.00	45.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	45.00	60.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	60.00	75.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	75.00	92.00		1	17.00			0.50	0.40	3.40	Only Desilt		

BOQ Item No	Description Chainage		Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit/ Remarks	Rate	Amount
	92.00	102.80		0	10.80			0.50	0.40	0.00	Balajikrupa Main Road		
	102.80	105.00		1	2.20			0.50	0.40	0.44	Only Desilt		
	105.00	120.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	120.00	135.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	135.00	150.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	150.00	165.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	165.00	180.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	180.00	195.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	195.00	210.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	210.00	225.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	225.00	239.50		1	14.50			0.50	0.40	2.90	Only Desilt		
	239.50	250.70		0	11.20			0.50	0.40	0.00	No Work		
	2nd Cross Road												
	LHS												
	0.00	15.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	15.00	30.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	30.00	45.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	45.00	60.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	60.00	75.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	75.00	90.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	90.00	105.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	105.00	120.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	120.00	135.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	135.00	145.00		1	10.00			0.50	0.40	2.00	Only Desilt		
	145.00	155.00		0	10.00			0.50	0.40	0.00	Balajikrupa Main Road		
	155.00	165.00		1	10.00			0.50	0.40	2.00	Only Desilt		
	165.00	180.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	180.00	195.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	195.00	210.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	210.00	225.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	225.00	240.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	240.00	255.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	255.00	270.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	270.00	285.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	285.00	300.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	300.00	303.50		1	3.50			0.50	0.40	0.70	Only Desilt		
	RHS												
	0.00	15.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	15.00	30.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	30.00	45.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	45.00	60.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	60.00	75.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	75.00	90.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	90.00	105.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	105.00	120.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	120.00	135.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	135.00	145.00		1	10.00			0.50	0.40	2.00	Only Desilt		
	145.00	155.00		0	10.00			0.50	0.40	0.00	Balajikrupa Main Road		
	155.00	165.00		1	10.00			0.50	0.40	2.00	Only Desilt		
	165.00	180.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	180.00	195.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	195.00	210.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	210.00	225.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	225 00	240.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	240.00	255.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	255.00	270.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	270.00	285.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	285.00	300.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	300.00	303.50		1	3.50			0.50	0.40	0.70	Only Desilt		
	3th Cross Road												
	LHS												
	0.00	15.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	15.00	30.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	30.00	45.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	45.00	62.70		1	17.70			0.50	0.40	3.54	Only Desilt		
	62.70	72.00		1	9.30			0.50	0.40	1.86	0.9 bs		
	72.00	81.30		1	9.30			0.50	0.40	1.86	0.9 bs		
	81.30	95.00		1	13.70			0.50	0.40	2.74	Only Desilt		
	95.00	110.00		1	15.00			0.50	0.40	3.00	Only Desilt		

BOQ Item No	Description Chainage		Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit/ Remarks	Rate	Amount
	110.00	125.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	125.00	135.00		1	10.00			0.50	0.40	2.00	Only Desilt		
	135.00	146.20		1	11.20			0.50	0.40	2.24	Only Desilt		
	146.20	157.00		0	10.80			0.50	0.40	0.00	Balajikrupa Main Road		
	157.00	161.00		1	4.00			0.50	0.40	0.80	Only Desilt		
	161.00	180.00		1	19.00			0.50	0.40	3.80	Only Desilt		
	180.00	195.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	195.00	210.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	210.00	225.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	225.00	240.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	240.00	255.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	255.00	265.00		1	10.00			0.50	0.40	2.00	Only Desilt		
	265.00	277.00		1	12.00			0.50	0.40	2.40	Only Desilt		
	277.00	286.00		0	9.00			0.50	0.40	0.00	No Work		
	286.00	305.00		1	19.00			0.50	0.40	3.80	Only Desilt		
	RHS												
	0.00	15.00		0	15.00			0.50	0.40	0.00	No Work		
	15.00	34.20		0	19.20			0.50	0.40	0.00	No Work		
	34.20	45.00		1	10.80			0.50	0.40	2.16	Only Desilt		
	45.00	62.70		1	17.70			0.50	0.40	3.54	Only Desilt		
	62.70	72.00		1	9.30			0.50	0.40	1.86	0.9 bs		
	72.00	81.30		1	9.30			0.50	0.40	1.86	0.9 bs		
	81.30	95.00		1	13.70			0.50	0.40	2.74	Only Desilt		
	95.00	110.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	110.00	125.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	125.00	135.00		1	10.00			0.50	0.40	2.00	Only Desilt		
	135.00	146.20		1	11.20			0.50	0.40	2.24	Only Desilt		
	146.20	157.00		0	10.80			0.50	0.40	0.00	Balajikrupa Main Road		
	157.00	161.00		1	4.00			0.50	0.40	0.80	Only Desilt		
	161.00	180.00		1	19.00			0.50	0.40	3.80	Only Desilt		
	180.00	195.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	195.00	210.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	210.00	225.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	225.00	240.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	240.00	255.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	255.00	265.00		1	10.00			0.50	0.40	2.00	Only Desilt		
	265.00	277.00		1	12.00			0.50	0.40	2.40	Only Desilt		
	277.00	296.00		1	19.00			0.50	0.40	3.80	Only Desilt		
	296.00	305.00		0	9.00			0.50	0.40	0.00	No Work		
	4th Cross Road												
	LHS												
	0.00	15.00		0	15.00			0.50	0.40	0.00	Only Desilt		
	15.00	34.20		0	19.20			0.50	0.40	0.00	Only Desilt		
	34.20	45.00		1	10.80			0.50	0.40	2.16	Only Desilt		
	45.00	62.70		1	17.70			0.50	0.40	3.54	Only Desilt		
	62.70	72.00		1	9.30			0.50	0.40	1.86	Only Desilt		
	72.00	81.30		1	9.30			0.50	0.40	1.86	Only Desilt		
	81.30	95.00		1	13.70			0.50	0.40	2.74	Only Desilt		
	95.00	110.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	110.00	125.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	125.00	135.00		1	10.00			0.50	0.40	2.00	Only Desilt		
	135.00	148.80		1	13.80			0.50	0.40	2.76	Only Desilt		
	148.80	159.30		0	10.50			0.50	0.40	0.00	Balajikrupa Main Road		
	159.30	161.00		1	1.70			0.50	0.40	0.34	Only Desilt		
	161.00	180.00		1	19.00			0.50	0.40	3.80	Only Desilt		
	180.00	195.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	195.00	210.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	210.00	225.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	225.00	246.00		1	21.00			0.50	0.40	4.20	Only Desilt		
	246.00	255.00		0	9.00			0.50	0.40	0.00	No Work		
	255.00	265.00		0	10.00			0.50	0.40	0.00	No Work		
	265.00	277.00		0	12.00			0.50	0.40	0.00	No Work		
	277.00	300.50		0	23.50			0.50	0.40	0.00	No Work		
	RHS												
	0.00	15.00		0	15.00			0.50	0.40	0.00	Only Desilt		
	15.00	34.20		0	19.20			0.50	0.40	0.00	Only Desilt		
	34.20	45.00		1	10.80			0.50	0.40	2.16	Only Desilt		
	45.00	62.70		1	17.70			0.50	0.40	3.54	Only Desilt		
	62.70	72.00		1	9.30			0.50	0.40	1.86	Only Desilt		

BOQ Item No	Description Chainage		Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit/ Remarks	Rate	Amount
	72.00	81.30		1	9.30			0.50	0.40	1.86	Only Desilt		
	81.30	95.00		1	13.70			0.50	0.40	2.74	Only Desilt		
	95.00	119.00		1	24.00			0.50	0.40	4.80	Only Desilt		
	119.00	125.00		0	6.00			0.50	0.40	0.00	No Work		
	125.00	140.00		0	15.00			0.50	0.40	0.00	No Work		
	140.00	148.80		1	8.80			0.50	0.40	1.76	Only Desilt		
	148.80	159.30		0	10.50			0.50	0.40	0.00	Balajikrupa Main Road		
	159.30	161.00		1	1.70			0.50	0.40	0.34	Only Desilt		
	161.00	180.00		1	19.00			0.50	0.40	3.80	Only Desilt		
	180.00	195.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	195.00	210.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	210.00	225.00		1	15.00			0.50	0.40	3.00	Only Desilt		
	225.00	246.00		1	21.00			0.50	0.40	4.20	Only Desilt		
	246.00	252.80		1	6.80			0.50	0.40	1.36	Only Desilt		
	252.80	261.50		0	8.70			0.50	0.40	0.00	No Work		
	261.50	277.00		1	15.50			0.50	0.40	3.10	Only Desilt		
	277.00	298.20		1	21.20			0.50	0.40	4.24	Only Desilt		
	6th Cross Road												
	LHS												
	0.00	13.40		0	13.40			0.50	0.40	0.00	No Work		
	13.40	25.80		1	12.40			0.50	0.40	2.48	deck slasb		
	25.80	38.00		1	12.20			0.50	0.40	2.44	Only Desilt		
	38.00	50.30		0	12.30			0.50	0.40	0.00	No Work		
	50.30	62.00		1	11.70			0.50	0.40	2.34	deck slasb		
	62.00	69.00		1	7.00			0.50	0.40	1.40	Open drain		
	69.00	74.20		1	5.20			0.50	0.40	1.04	1.2 bs		
	74.20	90.00		1	15.80			0.50	0.40	3.16	Only Desilt		
	90.00	100.00		1	10.00			0.50	0.40	2.00	Only Desilt		
	100.00	110.50		0	10.50			0.50	0.40	0.00	Balajikrupa Main Road		
	110.50	113.00		1	2.50			0.50	0.40	0.50	Open drain		
	113.00	129.50		1	16.50			0.50	0.40	3.30	0.9 bs		
	129.50	138.00		0	8.50			0.50	0.40	0.00	No Work		
	138.00	148.00		1	10.00			0.50	0.40	2.00	1.2 bs		
	148.00	157.00		1	9.00			0.50	0.40	1.80	0.9 pcs.		
	157.00	166.00		1	9.00			0.50	0.40	1.80	0.9 bs		
	166.00	170.00		1	4.00			0.50	0.40	0.80	Open drain		
	170.00	175.00		1	5.00			0.50	0.40	1.00	deck slasb		
	175.00	184.50		1	9.50			0.50	0.40	1.90	1.2 pcs		
	184.50	202.00		1	17.50			0.50	0.40	3.50	0.9 bs		
	202.00	222.00		1	20.00			0.50	0.40	4.00	0.9 bs		
	222.00	248.00		1	26.00			0.50	0.40	5.20	Open drain		
	248.00	258.50		0	10.50			0.50	0.40	0.00	No Work		
	RHS												
	0.00	13.40		0	13.40			0.50	0.40	0.00	No drain		
	13.40	25.80		1	12.40			0.50	0.40	2.48	Open drain		
	25.80	34.40		1	8.60			0.50	0.40	1.72	Only Desilt		
	34.40	38.00		1	3.60			0.50	0.40	0.72	deck slasb		
	38.00	50.30		1	12.30			0.50	0.40	2.46	deck slasb		
	50.30	59.50		1	9.20			0.50	0.40	1.84	Only Desilt		
	59.50	62.30		1	2.80			0.50	0.40	0.56	deck slasb		
	62.30	74.50		1	12.20			0.50	0.40	2.44	0.9 bs		
	74.50	100.00		1	25.50			0.50	0.40	5.10	Open drain		
	100.00	110.50		0	10.50			0.50	0.40	0.00	Balajikrupa Main Road		
	110.50	124.00		1	13.50			0.50	0.40	2.70	Open drain		
	124.00	135.00		1	11.00			0.50	0.40	2.20	Only Desilt		
	135.00	145.00		0	10.00			0.50	0.40	0.00	No Work		
	145.00	148.50		0	3.50			0.50	0.40	0.00	deck slasb		
	148.50	180.00		1	31.50			0.50	0.40	6.30	Open drain		
	180.00	197.00		1	17.00			0.50	0.40	3.40	0.9 bs		
	197.00	202.50		1	5.50			0.50	0.40	1.10	Only Desilt		
	202.50	208.00		0	5.50			0.50	0.40	0.00	deck slasb		
	208.00	212.00		1	4.00			0.50	0.40	0.80	1.2 bs		
	212.00	222.00		1	10.00			0.50	0.40	2.00	Open drain		
	222.00	233.00		0	11.00			0.50	0.40	0.00	No drain		
	233.00	250.00		1	17.00			0.50	0.40	3.40	Open drain		
	250.00	258.50		0	8.50			0.50	0.40	0.00	No work		
	7th Cross Road												
	LHS												
	0.00	10.00		0	10.00			0.50	0.40	0.00	No work		

BOQ Item No	Description Chainage		Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit/ Remarks	Rate	Amount
	10.00	24.00		0	14.00			0.50	0.40	0.00	No work		
	24.00	40.00		1	16.00			0.50	0.40	3.20	Open drain		
	40.00	55.00		1	15.00			0.50	0.40	3.00	Open drain		
	55.00	73.50		1	18.50			0.50	0.40	3.70	Open drain		
	73.50	80.50		1	7.00			0.50	0.40	1.40	Open drain		
	80.50	85.00		1	4.50			0.50	0.40	0.90	deck slasb		
	85.00	87.00		1	2.00			0.50	0.40	0.40	Open drain		
	87.00	97.00		1	10.00			0.50	0.40	2.00	0.9 bs		
	97.00	110.00		1	13.00			0.50	0.40	2.60	Open drain		
	110.00	125.00		1	15.00			0.50	0.40	3.00	Open drain		
	125.00	136.00		1	11.00			0.50	0.40	2.20	Open drain		
	136.00	146.00		0	10.00			0.50	0.40	0.00	Balajikrupa Main Road		
	146.00	156.40		1	10.40			0.50	0.40	2.08	0.9 bs		
	156.40	165.30		0	8.90			0.50	0.40	0.00	No work		
	165.30	174.50		0	9.20			0.50	0.40	0.00	deck slasb		
	174.50	184.00		1	9.50			0.50	0.40	1.90	0.9 bs		
	184.00	201.70		1	17.70			0.50	0.40	3.54	Open drain		
	201.70	211.00		0	9.30			0.50	0.40	0.00	No work		
	211.00	230.00		1	19.00			0.50	0.40	3.80	Open drain		
	230.00	245.00		1	15.00			0.50	0.40	3.00	Open drain		
	245.00	260.00		1	15.00			0.50	0.40	3.00	Open drain		
	260.00	266.00		1	6.00			0.50	0.40	1.20	Open drain		
	266.00	275.00		0	9.00			0.50	0.40	0.00	No work		
	275.00	294.00		0	19.00			0.50	0.40	0.00	deck slasb		
	294.00	307.50		0	13.50			0.50	0.40	0.00	No work		
	RHS												
	0.00	15.00		0	15.00			0.50	0.40	0.00	No work		
	15.00	30.00		0	15.00			0.50	0.40	0.00	No work		
	30.00	44.50		0	14.50			0.50	0.40	0.00	No work		
	44.50	49.00		0	4.50			0.50	0.40	0.00	No work		
	49.00	61.00		1	12.00			0.50	0.40	2.40	1.2 BS		
	61.00	73.00		0	12.00			0.50	0.40	0.00	No work		
	73.00	94.00		1	21.00			0.50	0.40	4.20	Open drain		
	94.00	111.50		1	17.50			0.50	0.40	3.50	0.9 B S		
	111.50	125.00		1	13.50			0.50	0.40	2.70	Open drain		
	125.00	136.00		1	11.00			0.50	0.40	2.20	Open drain		
	136.00	146.00		0	10.00			0.50	0.40	0.00	Balajikrupa Main Road		
	146.00	156.40		1	10.40			0.50	0.40	2.08	0.9 B S		
	156.40	159.50		1	3.10			0.50	0.40	0.62	deck slasb		
	159.50	171.60		0	12.10			0.50	0.40	0.00	deck slasb		
	171.60	184.00		1	12.40			0.50	0.40	2.48	Open drain		
	184.00	195.70		0	11.70			0.50	0.40	0.00	No work		
	195.70	208.00		1	12.30			0.50	0.40	2.46	0.9 BS		
	208.00	214.00		1	6.00			0.50	0.40	1.20	Open drain		
	214.00	220.60		1	6.60			0.50	0.40	1.32	deck slasb		
	220.60	230.00		1	9.40			0.50	0.40	1.88	0.9 BS		
	230.00	246.00		1	16.00			0.50	0.40	3.20	0.9 BS		
	246.00	257.00		1	11.00			0.50	0.40	2.20	Open drain		
	257.00	269.00		0	12.00			0.50	0.40	0.00	No work		
	269.00	281.00		0	12.00			0.50	0.40	0.00	deck slasb		
	281.00	288.00		1	7.00			0.50	0.40	1.40	0.9 BS		
	288.00	294.00		1	6.00			0.50	0.40	1.20	deck slasb		
	294.00	307.50		1	13.50			0.50	0.40	2.70	Open drain		
	8th Cross Road												
	LHS												
	0.00	21.00		1	21.00			0.50	0.40	4.20	Open drain		
	21.00	38.00		1	17.00			0.50	0.40	3.40	0.9 BS		
	38.00	56.50		1	18.50			0.50	0.40	3.70	Open drain		
	56.50	75.80		1	19.30			0.50	0.40	3.86	0.9 BS		
	75.80	84.00		0	8.20			0.50	0.40	0.00	deck slasb		
	84.00	93.00		1	9.00			0.50	0.40	1.80	Open drain		
	93.00	118.70		1	25.70			0.50	0.40	5.14	0.9 BS		
	118.70	136.00		1	17.30			0.50	0.40	3.46	Open drain		
	136.00	148.60		0	12.60			0.50	0.40	0.00	No work		
	RHS												
	0.00	11.00		1	11.00			0.50	0.40	2.20	Open drain		
	11.00	15.00		1	4.00			0.50	0.40	0.80	0.9 BS		
	15.00	30.00		1	15.00			0.50	0.40	3.00	0.9 BS		
	30.00	45.00		1	15.00			0.50	0.40	3.00	0.9 BS		
	45.00	60.00		1	15.00			0.50	0.40	3.00	0.9 BS		

BOQ Item No	Description Chainage		Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit/ Remarks	Rate	Amount
	60.00	75.00		1	15.00			0.50	0.40	3.00	0.9 BS		
	75.00	87.00		1	12.00			0.50	0.40	2.40	0.9 BS		
	87.00	99.50		0	12.50			0.50	0.40	0.00	deck slasb		
	99.50	112.00		1	12.50			0.50	0.40	2.50	0.9 BS		
	112.00	136.00		1	24.00			0.50	0.40	4.80	Open drain		
	136.00	148.60		0	12.60			0.50	0.40	0.00	No work		
	9th Cross Road												
	LHS												
	0.00	14.00		0	14.00			0.50	0.40	0.00	No drain		
	14.00	39.70		0	25.70			0.50	0.40	0.00	No work		
	39.70	58.00		1	18.30			0.50	0.40	3.66	0.9 bs		
	58.00	76.50		1	18.50			0.50	0.40	3.70	Open drain		
	76.50	94.00		1	17.50			0.50	0.40	3.50	0.9 bs		
	94.00	104.50		1	10.50			0.50	0.40	2.10	deck slasb		
	104.50	117.00		0	12.50			0.50	0.40	0.00	No work		
	117.00	141.50		1	24.50			0.50	0.40	4.90	Open drain		
	141.50	151.50		0	10.00			0.50	0.40	0.00	Balajikrupa Main Road		
	151.50	165.00		0	13.50			0.50	0.40	0.00	No work		
	165.00	180.00		0	15.00			0.50	0.40	0.00	No work		
	180.00	195.00		0	15.00			0.50	0.40	0.00	No work		
	195.00	210.00		0	15.00			0.50	0.40	0.00	No work		
	210.00	225.00		0	15.00			0.50	0.40	0.00	No work		
	225.00	240.00		0	15.00			0.50	0.40	0.00	No work		
	240.00	250.50		0	10.50			0.50	0.40	0.00	No work		
	250.50	265.00		1	14.50			0.50	0.40	2.90	Open drain		
	265.00	274.70		1	9.70			0.50	0.40	1.94	Open drain		
	274.70	290.80		0	16.10			0.50	0.40	0.00	No work		
	RHS												
	0.00	14.00		0	14.00			0.50	0.40	0.00	No drain		
	14.00	26.00		1	12.00			0.50	0.40	2.40	Only disilt		
	26.00	39.70		0	13.70			0.50	0.40	0.00	No work		
	39.70	49.00		1	9.30			0.50	0.40	1.86	0.9 bs		
	49.00	68.00		0	19.00			0.50	0.40	0.00	No work		
	68.00	80.00		1	12.00			0.50	0.40	2.40	Open drain		
	80.00	94.00		1	14.00			0.50	0.40	2.80	Open drain		
	94.00	117.00		0	23.00			0.50	0.40	0.00	No work		
	117.00	123.00		1	6.00			0.50	0.40	1.20	0.9 bs		
	123.00	141.50		1	18.50			0.50	0.40	3.70	Open drain		
	141.50	151.50		1	10.00			0.50	0.40	2.00	Balajikrupa Main Road		
	151.50	165.00		0	13.50			0.50	0.40	0.00	No work		
	165.00	180.00		0	15.00			0.50	0.40	0.00	No work		
	180.00	195.00		0	15.00			0.50	0.40	0.00	No work		
	195.00	210.00		0	15.00			0.50	0.40	0.00	No work		
	210.00	225.00		0	15.00			0.50	0.40	0.00	No work		
	225.00	235.00		0	10.00			0.50	0.40	0.00	No work		
	235.00	250.00		1	15.00			0.50	0.40	3.00	Open drain		
	250.00	265.00		1	15.00			0.50	0.40	3.00	Open drain		
	265.00	281.00		1	16.00			0.50	0.40	3.20	Open drain		
	281.00	290.80		0	9.80			0.50	0.40	0.00	No work		
	10th Cross Road												
	LHS												
	0.00	7.70		0	7.70			0.50	0.40	0.00	No work		
	7.70	16.70		1	9.00			0.50	0.40	1.80	Open drain		
	16.70	22.00		1	5.30			0.50	0.40	1.06	0.9 bs		
	22.00	35.00		1	13.00			0.50	0.40	2.60	Open drain		
	35.00	42.50		0	7.50			0.50	0.40	0.00	c/s road		
	42.50	62.00		0	19.50			0.50	0.40	0.00	Open drain		
	62.00	66.00		1	4.00			0.50	0.40	0.80	0.9 bs		
	66.00	71.50		0	5.50			0.50	0.40	0.00	deck slab		
	71.50	85.00		1	13.50			0.50	0.40	2.70	Open drain		
	85.00	107.20		1	22.20			0.50	0.40	4.44	Only disilt		
	107.20	120.00		1	12.80			0.50	0.40	2.56	deck slab		
	120.00	130.00		0	10.00			0.50	0.40	0.00	Balajikrupa Main Road		
	130.00	145.00		0	15.00			0.50	0.40	0.00	No work		
	145.00	148.00		1	3.00			0.50	0.40	0.60	Only disilt		
	148.00	156.00		1	8.00			0.50	0.40	1.60	Open drain		
	156.00	172.00		0	16.00			0.50	0.40	0.00	deck slab		
	172.00	186.00		0	14.00			0.50	0.40	0.00	No work		
	186.00	201.00		0	15.00			0.50	0.40	0.00	No work		
	201.00	213.80		1	12.80			0.50	0.40	2.56	Open drain		

BOQ Item No	Description Chainage		Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit/ Remarks	Rate	Amount
	213.80	232.00		0	18.20			0.50	0.40	0.00	No work		
	232.00	250.00		1	18.00			0.50	0.40	3.60	Only disilt		
	250.00	265.00		1	15.00			0.50	0.40	3.00	Only disilt		
	265.00	278.00		1	13.00			0.50	0.40	2.60	Only disilt		
	RHS												
	0.00	12.00		0	12.00			0.50	0.40	0.00	No work		
	12.00	25.00		1	13.00			0.50	0.40	2.60	Only disilt		
	25.00	35.00		1	10.00			0.50	0.40	2.00	Only disilt		
	35.00	39.00		1	4.00			0.50	0.40	0.80	Open drain		
	39.00	52.70		1	13.70			0.50	0.40	2.74	Only disilt		
	52.70	59.00		1	6.30			0.50	0.40	1.26	Only disilt		
	59.00	85.20		1	26.20			0.50	0.40	5.24	Only disilt		
	85.20	103.50		0	18.30			0.50	0.40	0.00	deck slab		
	103.50	120.00		1	16.50			0.50	0.40	3.30	Open drain		
	120.00	130.00		0	10.00			0.50	0.40	0.00	Balajikrupa Main Road		
	130.00	145.00		1	15.00			0.50	0.40	3.00	Only disilt		
	145.00	159.00		1	14.00			0.50	0.40	2.80	Only disilt		
	159.00	168.00		0	9.00			0.50	0.40	0.00	No work		
	168.00	185.00		1	17.00			0.50	0.40	3.40	Open drain		
	185.00	200.00		1	15.00			0.50	0.40	3.00	Open drain		
	200.00	215.00		1	15.00			0.50	0.40	3.00	Open drain		
	215.00	230.00		1	15.00			0.50	0.40	3.00	Open drain		
	230.00	248.00		1	18.00			0.50	0.40	3.60	Open drain		
	248.00	260.00		0	12.00			0.50	0.40	0.00	No work		
	260.00	278.00		0	18.00			0.50	0.40	0.00	No work		
	11th Cross Road												
	LHS												
	0.00	15.00		1	15.00			0.50	0.40	3.00	Open drain		
	15.00	26.00		0	11.00			0.50	0.40	0.00	No work		
	26.00	33.80		1	7.80			0.50	0.40	1.56	Open drain		
	33.80	50.00		1	16.20			0.50	0.40	3.24	Only disilt		
	50.00	70.00		1	20.00			0.50	0.40	4.00	Only disilt		
	70.00	88.00		1	18.00			0.50	0.40	3.60	Open drain		
	88.00	105.00		1	17.00			0.50	0.40	3.40	0.9 BS Slab		
	105.00	120.00		1	15.00			0.50	0.40	3.00	0.9 PCS Slab		
	120.00	135.00		1	15.00			0.50	0.40	3.00	Desilt only		
	135.00	153.00		1	18.00			0.50	0.40	3.60	Desilt only		
	153.00	171.00		0	18.00			0.50	0.40	0.00	No work		
	171.00	197.00		1	26.00			0.50	0.40	5.20	Open drain		
	197.00	214.00		0	17.00			0.50	0.40	0.00	No work		
	214.00	235.00		0	21.00			0.50	0.40	0.00	No work		
	RHS												
	0.00	10.70		1	10.70			0.50	0.40	2.14	0.9BS		
	10.70	30.00		0	19.30			0.50	0.40	0.00	No work		
	30.00	45.00		0	15.00			0.50	0.40	0.00	No work		
	45.00	60.00		0	15.00			0.50	0.40	0.00	No work		
	60.00	81.00		0	21.00			0.50	0.40	0.00	No work		
	81.00	90.00		0	9.00			0.50	0.40	0.00	BalajiKrupa main road		
	90.00	117.00		1	27.00			0.50	0.40	5.40	Desilt only		
	117.00	126.00		0	9.00			0.50	0.40	0.00	No work		
	126.00	155.00		1	29.00			0.50	0.40	5.80	Desilt only		
	155.00	187.50		1	32.50			0.50	0.40	6.50	Open drain		
	187.50	200.00		0	12.50			0.50	0.40	0.00	No work		
	200.00	214.00		0	14.00			0.50	0.40	0.00	No work		
	214.00	235.00		1	21.00			0.50	0.40	4.20	Open drain		
	Connected to 10th to Emerald												
	LHS												
	0.00	9.00		1	9.00			0.50	0.40	1.80	Open drain		
	9.00	16.70		1	7.70			0.50	0.40	1.54	0.9 BS		
	16.70	25.00		0	8.30			0.50	0.40	0.00	No Work		
	25.00	35.00		1	10.00			0.50	0.40	2.00	1.2BS		
	35.00	46.50		1	11.50			0.50	0.40	2.30	Open drain		
	46.50	59.00		0	12.50			0.50	0.40	0.00	No Work		
	RHS												
	0.00	26.50		1	26.50			0.50	0.40	5.30	0.9 BS		
	26.50	35.80		0	9.30			0.50	0.40	0.00	11th c/s Rd (No work)		
	35.80	46.50		0	10.70			0.50	0.40	0.00	No Work		
	46.50	59.00		1	12.50			0.50	0.40	2.50	Open drain		

BOQ Item No	Description Chainage		Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit/ Remarks	Rate	Amount
	Emerald 1st c/s Rd												
	LHS												
	0.00	15.00		1	15.00			0.50	0.40	3.00	Open drain		
	15.00	30.00		1	15.00			0.50	0.40	3.00	Open drain		
	30.00	45.00		1	15.00			0.50	0.40	3.00	Open drain		
	45.00	65.00		1	20.00			0.50	0.40	4.00	Open drain		
	65.00	73.50		0	8.50			0.50	0.40	0.00	c/s Rd (No work)		
	73.50	80.00		1	6.50			0.50	0.40	1.30	Open drain		
	80.00	95.00		1	15.00			0.50	0.40	3.00	Open drain		
	95.00	110.00		1	15.00			0.50	0.40	3.00	Open drain		
	110.00	125.00		1	15.00			0.50	0.40	3.00	Open drain		
	125.00	140.00		1	15.00			0.50	0.40	3.00	Open drain		
	140.00	155.00		1	15.00			0.50	0.40	3.00	Open drain		
	155.00	170.00		1	15.00			0.50	0.40	3.00	Open drain		
	170.00	185.00		1	15.00			0.50	0.40	3.00	Open drain		
	185.00	200.00		1	15.00			0.50	0.40	3.00	Open drain		
	200.00	215.00		1	15.00			0.50	0.40	3.00	Open drain		
	215.00	233.00		1	18.00			0.50	0.40	3.60	Open drain		
	233.00	241.00		0	8.00			0.50	0.40	0.00	c/s Rd (No work)		
	RHS												
	0.00	8.00		0	8.00			0.50	0.40	0.00	c/s Rd (No work)		
	8.00	22.00		0	14.00			0.50	0.40	0.00	No Work		
	22.00	48.10		1	26.10			0.50	0.40	5.22	0.9 BS		
	48.10	65.00		1	16.90			0.50	0.40	3.38	Open drain		
	65.00	73.50		1	8.50			0.50	0.40	1.70	Open drain		
	73.50	80.00		1	6.50			0.50	0.40	1.30	Open drain		
	80.00	95.00		1	15.00			0.50	0.40	3.00	Open drain		
	95.00	110.00		1	15.00			0.50	0.40	3.00	Open drain		
	110.00	125.00		1	15.00			0.50	0.40	3.00	Open drain		
	125.00	140.00		1	15.00			0.50	0.40	3.00	Open drain		
	140.00	155.00		1	15.00			0.50	0.40	3.00	Open drain		
	155.00	170.00		1	15.00			0.50	0.40	3.00	Open drain		
	170.00	185.00		1	15.00			0.50	0.40	3.00	Open drain		
	185.00	200.00		1	15.00			0.50	0.40	3.00	Open drain		
	200.00	215.00		1	15.00			0.50	0.40	3.00	Open drain		
	215.00	233.00		1	18.00			0.50	0.40	3.60	Open drain		
	233.00	241.00		1	8.00			0.50	0.40	1.60	Open drain		
	Culvert Desilt MS Nagara												
	Pristine Medows Opposite			1	8.10			0.65	0.50	2.63			
	6th Cross MS Nagara			1	8.10			0.65	0.50	2.63			
	MN Guru Akshatha			1	7.40			0.65	0.50	2.41			
	Gokulum Apartment Opp.			1	7.40			0.65	0.50	2.41			
	JS Mart Opp.			1	6.80			0.65	0.50	2.21			
	1st Cross in Manjunatha layout Connected to Manjunatha Layout Mn Rd												
	LHS												
	0.00	15.00		1	15.00			0.50	0.45	3.38	Open drain		
	15.00	30.00		1	15.00			0.50	0.45	3.38	Open drain		
	30.00	38.00		1	8.00			0.50	0.45	1.80	Open drain		
	38.00	52.00		1	14.00			0.50	0.45	3.15	Open drain		
	52.00	57.90		1	5.90			0.50	0.45	1.33	Open drain		
	RHS												
	0.00	15.00		1	15.00			0.50	0.45	3.38	Open drain		
	15.00	30.00		1	15.00			0.50	0.45	3.38	Open drain		
	30.00	38.00		1	8.00			0.50	0.45	1.80	Open drain		
	38.00	52.00		1	14.00			0.50	0.45	3.15	Open drain		
	52.00	57.90		1	5.90			0.50	0.45	1.33	Open drain		
	3rd Cross in Manjunatha layout Connected to Manjunatha Layout Mn Rd												
	LHS												
	0 00	15.00		1	15.00			0.50	0.45	3.38	Open drain		
	15.00	36.00		1	21.00			0.50	0.45	4.73	Open drain		
	36.00	45.00		0	9.00			0.50	0.45	0.00	No Work		
	45.00	59.00		0	14.00			0.50	0.45	0.00	No Work		
	RHS												
	0.00	15.00		1	15.00			0.50	0.45	3.38	Open drain		
	15.00	30.00		1	15.00			0.50	0.45	3.38	Open drain		
	30.00	47.00		1	17.00			0.50	0.45	3.83	Open drain		
	47.00	59.00		0	12.00			0.50	0.45	0.00	No Work		

BOQ Item No	Description Chainage		Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit/ Remarks	Rate	Amount
	Muneshwaraswamy Temple Opp.Rd												
	(Beside Appaji Café)												
	LHS												
	0.00	3.00		0	3.00			0.50	0.45	0.00	No Drain		
	3.00	6.00		1	3.00			0.50	0.45	0.68	Open drain		
	6.00	15.00		1	9.00			0.50	0.45	2.03	Open drain		
	15.00	30.00		1	15.00			0.50	0.45	3.38	Open drain		
	30.00	45.00		1	15.00			0.50	0.45	3.38	Open drain		
	45.00	60.00		1	15.00			0.50	0.45	3.38	Open drain		
	60.00	75.00		1	15.00			0.50	0.45	3.38	Open drain		
	75.00	90.00		1	15.00			0.50	0.45	3.38	Open drain		
	90.00	102.80		1	12.80			0.50	0.45	2.88	Open drain		
	RHS												
	0.00	3.00		0	3.00			0.50	0.45	0.00	No Drain		
	3.00	6.00		1	3.00			0.50	0.45	0.68	Open drain		
	6.00	15.00		1	9.00			0.50	0.45	2.03	Open drain		
	15.00	30.00		1	15.00			0.50	0.45	3.38	Open drain		
	30.00	45.00		1	15.00			0.50	0.45	3.38	Open drain		
	45.00	60.00		1	15.00			0.50	0.45	3.38	Open drain		
	60.00	75.00		1	15.00			0.50	0.45	3.38	Open drain		
	75.00	90.00		1	15.00			0.50	0.45	3.38	Open drain		
	90.00	102.80		1	12.80			0.50	0.45	2.88	Open drain		
	17th Cross Road (Connected to GKVK Double Road)												
	LHS												
	0.00	15.00	L/S	1	15.00			0.85	0.60	7.65	Open drain		
	15.00	30.00	L/S	1	15.00			0.50	0.60	4.50	Open drain		
	30.00	46.00	L/S	1	16.00			0.50	0.60	4.80	Open drain		
	Basavalingappa Nagara												
	LHS(6th A and 6th B)												
	0.00	10.50		1	10.50			0.50	0.45	2.36	Open drain		
	10.50	26.00		0	15.50			0.50	0.45	0.00	No Work		
	26.00	29.50		1	3.50			0.50	0.45	0.79	Open drain		
	29.50	35.40		1	5.90			0.50	0.45	1.33	1.2 BS slab		
	35.40	39.50		0	4.10			0.50	0.45	0.00	No Work		
	39.50	55.20		1	15.70			0.50	0.45	3.53	1.2 BS slab		
	55.20	65.90		1	10.70			0.50	0.45	2.41	Open drain		
	65.90	75.00		0	9.10			0.50	0.45	0.00	c/s Road		
	75.00	90.00		1	15.00			0.50	0.45	3.38	0.9 BS slab		
	90.00	105.00		1	15.00			0.50	0.45	3.38	0.9 BS slab		
	105.00	118.70		1	13.70			0.50	0.45	3.08	0.9 BS slab		
	118.70	122.90		1	4.20			0.50	0.45	0.95	Open drain		
	122.90	129.00		1	6.10			0.50	0.45	1.37	0.9 BS slab		
	129.00	137.80		0	8.80			0.50	0.45	0.00	No Work		
	137.80	147.80		1	10.00			0.50	0.45	2.25	1.2 BS slab		
	147.80	157.60		1	9.80			0.50	0.45	2.21	Open drain		
	157.60	161.00		1	3.40			0.50	0.45	0.77	0.9 BS slab		
	161.00	175.70		1	14.70			0.50	0.45	3 31	Open drain		
	175.70	178.00		1	2.30			0.50	0.45	0.52	1.2 BS slab		
	178.00	180.00		1	2.00			0.50	0.45	0.45	Open drain		
	180.00	203.20		1	23.20			0.50	0.45	5.22	0.9 BS slab		
	203.20	220.00		1	16.80			0.50	0.45	3.78	1.2 BS slab		
	220.00	229.50		1	9.50			0.50	0.45	2.14	0.9 BS slab		
	229.50	236.00		0	6.50			0.50	0.45	0.00	No Work		
	236.00	258.20		1	22.20			0.50	0.45	5.00	Open drain		
	258.20	271.00		0	12.80			0.50	0.45	0.00	No Work		
	RHS(6th A and 6th B)												
	0.00	18.20		0	18.20			0.50	0.45	0.00	No Work		
	18.20	27.80		1	9.60			0.50	0.45	2.16	1.2 BS slab		
	27.80	30.00		0	2.20			0.50	0.45	0.00	No Work		
	30.00	45.40		1	15.40			0.50	0.45	3.47	Open drain		
	45.40	65.90		1	20.50			0.50	0.45	4.61	1.2 BS slab		
	65.90	75.00		0	9.10			0.50	0.45	0.00	c/s Road		
	75.00	82.10		1	7.10			0.50	0.45	1.60	Open drain		
	82.10	90.00		1	7.90			0.50	0.45	1.78	No Work		
	90.00	94.80		1	4.80			0.50	0.45	1.08	0.9 BS slab		
	94.80	106.80		1	12.00			0.50	0.45	2.70	1.2 BS slab		
	106.80	122.20		1	15.40			0.50	0.45	3.47	Open drain		
	122.20	131.70		1	9.50			0.50	0.45	2.14	1.2 BS slab		
	131.70	150.00		0	18.30			0.50	0.45	0.00	No Work		
	150.00	166.00		0	16.00			0.50	0.45	0.00	No Work		
	166.00	180.00		1	14.00			0.50	0.45	3.15	Open drain		

BOQ Item No	Description Chainage		Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit/ Remarks	Rate	Amount
	180.00	195.00		1	15.00			0.50	0.45	3.38	Open drain		
	195.00	217.00		1	22.00			0.50	0.45	4.95	Open drain		
	217.00	221.60		1	4.60			0.50	0.45	1.04	1.2 BS slab		
	221.60	227.30		1	5.70			0.50	0.45	1.28	Open drain		
	227.30	254.50		1	27.20			0.50	0.45	6.12	1.2 BS slab		
	254.50	258.20		1	3.70			0.50	0.45	0.83	Deck slab		
	258.20	267.40		1	9.20			0.50	0.45	2.07	0.9 BS slab		
	267.40	271.00		1	3.60			0.50	0.45	0.81	Only desilt		
	Basavalingappa Nagara												
	LHS(5th A and 5th B)												
	0.00	9.20		1	9.20			0.50	0.45	2.07	1.2 BS slab		
	9.20	32.70		1	23.50			0.50	0.45	5.29	Open drain		
	32.70	57.20		1	24.50			0.50	0.45	5.51	1.2 BS slab		
	57.20	65.70		1	8.50			0.50	0.45	1.91	Open drain		
	65.70	74.50		0	8.80			0.50	0.45	0.00	c/s Road		
	74.50	98.60		1	24.10			0.50	0.45	5.42	No Work		
	98.60	108.80		1	10.20			0.50	0.45	2.30	1.2 BS slab		
	108.80	122.00		1	13.20			0.50	0.45	2.97	Open drain		
	122.00	131.00		1	9.00			0.50	0.45	2.03	0.9 BS slab		
	131.00	140.50		0	9.50			0.50	0.45	0.00	No Work		
	140.50	156.60		1	16.10			0.50	0.45	3.62	1.2 BS slab		
	156.60	164.00		0	7.40			0.50	0.45	0.00	No Work		
	164.00	192.00		0	28.00			0.50	0.45	0.00	No Work		
	192.00	202.00		1	10.00			0.50	0.45	2.25	Open drain		
	202.00	225.00		0	23.00			0.50	0.45	0.00	No Work		
	225.00	249.60		0	24.60			0.50	0.45	0.00	No drain		
	RHS(5th A and 5th B)												
	0.00	65.70		0	65.70			0.50	0.45	0.00	No drain		
	65.70	74.50		0	8.80			0.50	0.45	0.00	c/s Road		
	74.50	85.10		1	10.60			0.50	0.45	2.39	Open drain		
	85.10	94.60		1	9.50			0.50	0.45	2.14	0.9 PCS		
	94.60	109.60		1	15.00			0.50	0.45	3.38	Open drain		
	109.60	131.00		1	21.40			0.50	0.45	4.82	0.9 BS slab		
	131.00	139.50		1	8.50			0.50	0.45	1.91	Open drain		
	139.50	146.00		1	6.50			0.50	0.45	1.46	0.9 BS slab		
	146.00	161.00		0	15.00			0.50	0.45	0.00	Deck slab		
	161.00	170.90		1	9.90			0.50	0.45	2.23	Open drain		
	170.90	175.50		1	4.60			0.50	0.45	1.04	0.9 BS slab		
	175.50	189.30		1	13.80			0.50	0.45	3.11	Open drain		
	189.30	200.00		0	10.70			0.50	0.45	0.00	No Work		
	200.00	225.00		0	25.00			0.50	0.45	0.00	No Work		
	225.00	249.60		0	24.60			0.50	0.45	0.00	No drain		
	Basavalingappa Nagara												
	LHS(4th B)												
	0.00	14.70		1	14.70			0.50	0.45	3.31	1.2 BS slab		
	14.70	20.20		1	5.50			0.50	0.45	1.24	Open drain		
	20.20	28.20		1	8.00			0.50	0.45	1.80	1.2 BS slab		
	28.20	38.80		1	10.60			0.50	0.45	2.39	Open drain		
	38.80	48.00		1	9.20			0.50	0.45	2.07	Open drain		
	48.00	71.00		1	23.00			0.50	0.45	5.18	1.2 BS slab		
	71.00	85.50		1	14.50			0.50	0.45	3.26	Open drain		
	85.50	94.20		1	8.70			0.50	0.45	1.96	0.9 BS slab		
	94.20	117.00		1	22.80			0.50	0.45	5.13	Open drain		
	117.00	140.80		0	23.80			0.50	0.45	0.00	No work		
	140.80	147.30		1	6.50			0.50	0.45	1.46	Open drain		
	147.30	160.00		0	12.70			0.50	0.45	0.00	No work		
	160.00	170.20		1	10.20			0.50	0.45	2.30	0.9 BS slab		
	170.20	171.60		0	1.40			0.50	0.45	0.00	No work		
	RHS(4th B)												
	0.00	18.70		1	18.70			0.50	0.45	4.21	Open drain		
	18.70	31.70		1	13.00			0.50	0.45	2.93	0.9 BS slab		
	31.70	38.00		1	6.30			0.50	0.45	1.42	Open drain		
	38.00	45.50		1	7.50			0.50	0.45	1.69	0.9 BS slab		
	45.50	56.00		1	10.50			0.50	0.45	2.36	Open drain		
	56.00	71.00		1	15.00			0.50	0.45	3.38	0.9 BS slab		
	71.00	82.50		0	11.50			0.50	0.45	0.00	No work		
	82.50	103.40		1	20.90			0.50	0.45	4.70	Open drain		
	103.40	117.00		0	13.60			0.50	0.45	0.00	No work		
	117.00	126.30		1	9.30			0.50	0.45	2.09	Open drain		
	126.30	140.80		0	14.50			0.50	0.45	0.00	No work		
	140.80	168.40		1	27.60			0.50	0.45	6.21	0.9 BS slab		
	168.40	171.60		0	3.20			0.50	0.45	0.00	No work		

BOQ Item No	Description Chainage		Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit/ Remarks	Rate	Amount
	Basavalingappa Nagara												
	LHS(3rd A and 3rd B)												
	0.00	60.70		0	60.70			0.50	0.45	0.00	No work		
	60.70	70.30		0	9.60			0.50	0.45	0.00	c/s Road		
	70.30	85.00		1	14.70			0.50	0.45	3.31	Open drain		
	85.00	100.00		1	15.00			0.50	0.45	3.38	Open drain		
	100.00	115.00		1	15.00			0.50	0.45	3.38	Open drain		
	115.00	123.60		1	8.60			0.50	0.45	1.94	Open drain		
	123.60	152.70		0	29.10			0.50	0.45	0.00	No work		
	RHS(3rd A and 3rd B)												
	0.00	13.00		1	13.00			0.50	0.45	2.93	Open drain		
	13.00	20.00		1	7.00			0.50	0.45	1.58	1.2 BS slab		
	20.00	21.80		1	1.80			0.50	0.45	0.41	Open drain		
	21.80	36.00		1	14.20			0.50	0.45	3.20	1.2 BS slab		
	36.00	40.00		1	4.00			0.50	0.45	0.90	Open drain		
	40.00	48.70		1	8.70			0.50	0.45	1.96	0.9 BS slab		
	48.70	60.70		1	12.00			0.50	0.45	2.70	Open drain		
	60.70	70.30		0	9.60			0.50	0.45	0.00	c/s Road		
	70.30	75.00		1	4.70			0.50	0.45	1.06	Open drain		
	75.00	90.00		1	15.00			0.50	0.45	3.38	Open drain		
	90.00	105.00		1	15.00			0.50	0.45	3.38	Open drain		
	105.00	120.00		1	15.00			0.50	0.45	3.38	Open drain		
	120.00	130.50		1	10.50			0.50	0.45	2.36	Open drain		
	130.50	144.50		0	14.00			0.50	0.45	0.00	No work		
	144.50	148.60		1	4.10			0.50	0.45	0.92	Open drain		
	148.60	152.70		0	4.10			0.50	0.45	0.00	No work		
	New BS Drain												
	Agrahara Layout Main Road (Ch. From Agrahara Main Rd)												
	LHS												
	0.00	15.00		1	15.00			0.50	0.50	3.75			
	15.00	39.00		1	24.00			0.50	0.50	6.00			
	39.00	55.50		1	16.50			0.50	0.50	4.13			
	55.50	63.00		0	7.50			0.50	0.50	0.00	c/s Rd		
	63.00	75.00		1	12.00			0.50	0.50	3.00			
	75.00	90.00		1	15.00			0.50	0.50	3.75			
	90.00	97.00		1	7.00			0.50	0.50	1.75			
	97.00	104.60		1	7.60			0.50	0.50	1.90			
	104.60	120.00		1	15.40			0.50	0.50	3.85			
	120.00	135.00		1	15.00			0.50	0.50	3.75			
	135.00	150.00		1	15.00			0.50	0.50	3.75			
	150.00	162.50		1	12.50			0.50	0.50	3.13			
	162.50	178.50		1	16.00			0.50	0.50	4.00			
	178.50	190.00		1	11.50			0.50	0.50	2.88			
	190.00	205.00		1	15.00			0.50	0.50	3.75			
	205.00	226.00		1	21.00			0.50	0.50	5.25			
	226.00	233.00		0	7.00			0.50	0.50	0.00	c/s Rd		
	233.00	252.00		1	19.00			0.50	0.50	4.75			
	252.00	261.00		0	9.00			0.50	0.50	0.00	c/s Rd		
	261.00	277.00		1	16.00			0.50	0.50	4.00			
	277.00	291.00		1	14.00			0.50	0.50	3.50			
	291.00	300.00		1	9.00			0.50	0.50	2.25			
	300.00	315.00		1	15.00			0.50	0.50	3.75			
	315.00	330.00		1	15.00			0.50	0.50	3.75			
	330.00	345.00		1	15.00			0.50	0.50	3.75			
	345.00	360.00		1	15.00			0.50	0.50	3.75			
	360.00	375.00		1	15.00			0.50	0.50	3.75			
	375.00	390.00		1	15.00			0.50	0.50	3.75			
	390.00	405.00		1	15.00			0.50	0.50	3.75			
	405.00	420.00		1	15.00			0.50	0.50	3.75			
	420.00	435.00		1	15.00			0.50	0.50	3.75			
	435.00	448.00		1	13.00			0.50	0.50	3.25			
	RHS												
	0.00	15.00		1	15.00			0.50	0.50	3.75			
	15.00	30.00		1	15.00			0.50	0.50	3.75			
	30.00	45.00		1	15.00			0.50	0.50	3.75			
	45.00	59.20		1	14.20			0.50	0.50	3.55			
	59.20	67.00		0	7.80			0.50	0.50	0.00	c/s Rd(1st Mn Kuvempu Layout)		
	67.00	100.00		1	33.00			0.50	0.50	8.25			
	100.00	108.50		0	8.50			0.50	0.50	0.00	c/s Rd(2nd Mn Kuvempu Layout)		
	108.50	135.00		1	26.50			0.50	0.50	6.63			

BOQ Item No	Description Chainage		Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit/ Remarks	Rate	Amount
	135.00	142.50		0	7.50			0.50	0.50	0.00	c/s Rd(3rd Mn Kuvempu Layout) 1.5PCS		
	142.50	150.00		1	7.50			0.50	0.50	1.88			
	150.00	165.00		1	15.00			0.50	0.50	3.75			
	165.00	180.00		1	15.00			0.50	0.50	3.75			
	180.00	195.00		1	15.00			0.50	0.50	3.75			
	195.00	214.00		1	19.00			0.50	0.50	4.75			
	214.00	221.00		1	7.00			0.50	0.50	1.75			
	221.00	264.00		1	43.00			0.50	0.50	10.75			
	264.00	291.00		1	27.00			0.50	0.50	6.75			
	291.00	300.00		1	9.00			0.50	0.50	2.25			
	300.00	328.50		1	28.50			0.50	0.50	7.13			
	328.50	333.00		1	4.50			0.50	0.50	1.13			
	333.00	362.00		1	29.00			0.50	0.50	7.25			
	362.00	380.00		1	18.00			0.50	0.50	4.50			
	380.00	395.00		1	15.00			0.50	0.50	3.75			
	395.00	416.00		1	21.00			0.50	0.50	5.25			
	416.00	428.00		1	12.00			0.50	0.50	3.00			
	428.00	439.00		0	11.00			0.50	0.50	0.00	(c/s Rd)		
	439.00	450.00		1	11.00			0.50	0.50	2.75			
	450.00	465.00		1	15.00			0.50	0.50	3.75			
	465.00	480.00		1	15.00			0.50	0.50	3.75			
	480.00	495.00		1	15.00			0.50	0.50	3.75			
	495.00	510.00		1	15.00			0.50	0.50	3.75			
	510.00	525.00		1	15.00			0.50	0.50	3.75			
	Hegdenagar Surrounding Area												
	BS drain Desilt												
	BDS Layout 1st A cross												
	LHS												
	0.00	15.00	L/S	0	15.00			0.60	0.40	0.00			
	15.00	30.00	L/S	0	15.00			0.60	0.40	0.00			
	30.00	45.00	L/S	0	15.00			0.60	0.40	0.00			
	45.00	55.30	L/S	0	10.30			0.60	0.40	0.00			
	55.30	77.00	L/S	0	21.70			0.60	0.40	0.00	No Work (Litigation)		
	77.00	87.00	L/S	0	10.00			0.60	0.40	0.00	No drain		
	87.00	102.00	L/S	1	15.00			0.60	0.40	3.60			
	102.00	117.00	L/S	1	15.00			0.60	0.40	3.60			
	117.00	132.00	L/S	1	15.00			0.60	0.40	3.60			
	132.00	147.00	L/S	1	15.00			0.60	0.40	3.60			
	147.00	162.00	L/S	1	15.00			0.60	0.40	3.60			
	162.00	177.00	L/S	1	15.00			0.60	0.40	3.60			
	177.00	192.00	L/S	1	15.00			0.60	0.40	3.60			
	192.00	207.00	L/S	1	15.00			0.60	0.40	3.60			
	207.00	222.00	L/S	1	15.00			0.60	0.40	3.60			
	222.00	237.00	L/S	1	15.00			0.60	0.40	3.60			
	237.00	252.00	L/S	1	15.00			0.60	0.40	3.60			
	252.00	267.00	L/S	1	15.00			0.60	0.40	3.60			
	267.00	282.00	L/S	1	15.00			0.60	0.40	3.60			
	282.00	297.00	L/S	1	15.00			0.60	0.40	3.60			
	297.00	312.00	L/S	1	15.00			0.60	0.40	3.60			
	312.00	327.00	L/S	1	15.00			0.60	0.40	3.60			
	327.00	342.00	L/S	1	15.00			0.60	0.40	3.60			
	342.00	357.00	L/S	1	15.00			0.60	0.40	3.60			
	357.00	372.00	L/S	1	15.00			0.60	0.40	3.60			
	372.00	387.00	L/S	1	15.00			0.60	0.40	3.60			
	387.00	402.00	L/S	1	15.00			0.60	0.40	3.60			
	402.00	417.00	L/S	1	15.00			0.60	0.40	3.60			
	417.00	432.00	L/S	1	15.00			0.60	0.40	3.60			
	432.00	447.00	L/S	1	15.00			0.60	0.40	3.60			
	RHS												
	0.00	15.00	R/S	1	15.00			0.60	0.40	3.60			
	15.00	30.00	R/S	1	15.00			0.60	0.40	3.60			
	30.00	45.00	R/S	1	15.00			0.60	0.40	3.60			
	45.00	55.30	R/S	1	10.30			0.60	0.40	2.47			
	55.30	77.00	R/S	0	21.70			0.60	0.40	0.00	No Work (Litigation)		
	77.00	92.00	R/S	1	15.00			0.60	0.40	3.60			
	92.00	107.00	R/S	1	15.00			0.60	0.40	3.60			
	107.00	122.00	R/S	1	15.00			0.60	0.40	3.60			
	122.00	137.00	R/S	1	15.00			0.60	0.40	3.60			
	137.00	152.00	R/S	1	15.00			0.60	0.40	3.60			

BOQ Item No	Description Chainage		Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit/ Remarks	Rate	Amount
	152.00	167.00	R/S	1	15.00			0.60	0.40	3.60			
	167.00	182.00	R/S	1	15.00			0.60	0.40	3.60			
	182.00	197.00	R/S	1	15.00			0.60	0.40	3.60			
	197.00	212.00	R/S	1	15.00			0.60	0.40	3.60			
	212.00	227.00	R/S	1	15.00			0.60	0.40	3.60			
	227.00	242.00	R/S	1	15.00			0.60	0.40	3.60			
	242.00	248.80	R/S	1	6.80			0.60	0.40	1.63			
	248.80	258.80	R/S	0	10.00			0.60	0.40	0.00	No Work (c/s Rd)		
	258.80	273.80	R/S	1	15.00			0.60	0.40	3.60			
	273.80	288.80	R/S	1	15.00			0.60	0.40	3.60			
	288.80	303.80	R/S	1	15.00			0.60	0.40	3.60			
	303.80	318.80	R/S	1	15.00			0.60	0.40	3.60			
	318.80	333.80	R/S	1	15.00			0.60	0.40	3.60			
	333.80	348.80	R/S	1	15.00			0.60	0.40	3.60			
	348.80	363.80	R/S	1	15.00			0.60	0.40	3.60			
	363.80	370.00	R/S	1	6.20			0.60	0.40	1.49			
	370.00	385.00	R/S	1	15.00			0.60	0.40	3.60			
	385.00	400.00	R/S	1	15.00			0.60	0.40	3.60			
	400.00	415.00	R/S	1	15.00			0.60	0.40	3.60			
	415.00	430.00	R/S	1	15.00			0.60	0.40	3.60			
	430.00	447.00	R/S	1	17.00			0.60	0.40	4.08			
	BDS Layout 1st cross Rd												
	LHS												
	0.00	12.00	L/S	1	12.00			0.60	0.40	2.88			
	12.00	30.00	L/S	1	18.00			0.60	0.40	4.32			
	30.00	60.70	L/S	1	30.70			0.60	0.40	7.37			
	60.70	84.30	L/S	1	23.60			0.60	0.40	5.66			
	84.30	95.50	L/S	1	11.20			0.60	0.40	2.69			
	95.50	110.00	L/S	1	14.50			0.60	0.40	3.48			
	110.00	129.00	L/S	1	19.00			0.60	0.40	4.56			
	129.00	150.00	L/S	1	21.00			0.60	0.40	5.04			
	150.00	171.00	L/S	1	21.00			0.60	0.40	5.04			
	RHS												
	0.00	12.00	R/S	1	12.00			0.60	0.40	2.88			
	12.00	30.60	R/S	1	18.60			0.60	0.40	4.46			
	30.60	49.60	R/S	1	19.00			0.60	0.40	4.56			
	49.60	60.00	R/S	1	10.40			0.60	0.40	2.50			
	60.00	75.00	R/S	1	15.00			0.60	0.40	3.60			
	75.00	95.50	R/S	1	20.50			0.60	0.40	4.92			
	95.50	110.00	R/S	1	14.50			0.60	0.40	3.48			
	110.00	129.00	R/S	1	19.00			0.60	0.40	4.56			
	129.00	150.00	R/S	1	21.00			0.60	0.40	5.04			
	150.00	171.00	R/S	1	21.00			0.60	0.40	5.04			
	BDS Layout 2nd cross Rd												
	LHS												
	0.00	16.00	L/S	1	16.00			0.60	0.40	3.84			
	16.00	30.00	L/S	1	14.00			0.60	0.40	3.36			
	30.00	40.00	L/S	1	10.00			0.60	0.40	2.40			
	40.00	52.00	L/S	1	12.00			0.60	0.40	2.88			
	52.00	65.00	L/S	1	13.00			0.60	0.40	3.12			
	65.00	75.00	L/S	1	10.00			0.60	0.40	2.40			
	75.00	88.00	L/S	1	13.00			0.60	0.40	3.12			
	88.00	95.00	L/S	1	7.00			0.60	0.40	1.68			
	95.00	110.00	L/S	1	15.00			0.60	0.40	3.60			
	110.00	121.60	L/S	1	11.60			0.60	0.40	2.78			
	121.60	135.00	L/S	1	13.40			0.60	0.40	3.22			
	135.00	150.00	L/S	1	15.00			0.60	0.40	3.60			
	150.00	158.70	L/S	1	8.70			0.60	0.40	2.09			
	RHS												
	0.00	26.00	R/S	1	26.00			0.60	0.40	6.24			
	26.00	35.00	R/S	1	9.00			0.60	0.40	2.16			
	35.00	45.00	R/S	1	10.00			0.60	0.40	2.40			
	45.00	59.80	R/S	1	14.80			0.60	0.40	3.55			
	59.80	75.50	R/S	1	15.70			0.60	0.40	3.77			
	75.50	90.00	R/S	1	14.50			0.60	0.40	3.48			
	90.00	100.00	R/S	1	10.00			0.60	0.40	2.40			
	100.00	115.00	R/S	1	15.00			0.60	0.40	3.60			
	115.00	121.60	R/S	1	6.60			0.60	0.40	1.58			
	121.60	130.00	R/S	1	8.40			0.60	0.40	2.02			
	130.00	145.00	R/S	1	15.00			0.60	0.40	3.60			

BOQ Item No	Description		Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit/ Remarks	Rate	Amount
	Chainage												
	145.00	158.70	R/S	1	13.70			0.60	0.40	3.29			
	BDS Layout 3rd cross Rd												
	LHS												
	0.00	15.00	L/S	1	15.00			0.60	0.40	3.60			
	15.00	30.00	L/S	1	15.00			0.60	0.40	3.60			
	30.00	45.00	L/S	1	15.00			0.60	0.40	3.60			
	45.00	60.00	L/S	1	15.00			0.60	0.40	3.60			
	60.00	75.00	L/S	1	15.00			0.60	0.40	3.60			
	75.00	90.00	L/S	1	15.00			0.60	0.40	3.60			
	90.00	96.50	L/S	1	6.50			0.60	0.40	1.56			
	96.50	106.40	L/S	1	9.90			0.60	0.40	2.38			
	106.40	120.00	L/S	1	13.60			0.60	0.40	3.26			
	120.00	135.00	L/S	1	15.00			0.60	0.40	3.60			
	135.00	149.20	L/S	1	14.20			0.60	0.40	3.41			
	149.20	158.60	L/S	0	9.40			0.60	0.40	0.00	No Work		
	158.60	170.00	L/S	1	11.40			0.60	0.40	2.74			
	170.00	185.00	L/S	1	15.00			0.60	0.40	3.60			
	185.00	199.70	L/S	1	14.70			0.60	0.40	3.53			
	199.70	210.00	L/S	1	10.30			0.60	0.40	2.47			
	210.00	225.00	L/S	1	15.00			0.60	0.40	3.60			
	225.00	240.00	L/S	1	15.00			0.60	0.40	3.60			
	240.00	255.00	L/S	1	15.00			0.60	0.40	3.60			
	255.00	270.00	L/S	1	15.00			0.60	0.40	3.60			
	270.00	285.00	L/S	1	15.00			0.60	0.40	3.60			
	285.00	300.00	L/S	1	15.00			0.60	0.40	3.60			
	300.00	315.00	L/S	1	15.00			0.60	0.40	3.60			
	315.00	330.00	L/S	1	15.00			0.60	0.40	3.60			
	330.00	345.00	L/S	1	15.00			0.60	0.40	3.60			
	345.00	360.00	L/S	1	15.00			0.60	0.40	3.60			
	360.00	375.00	L/S	1	15.00			0.60	0.40	3.60			
	375.00	390.00	L/S	1	15.00			0.60	0.40	3.60			
	390.00	401.00	L/S	1	11.00			0.60	0.40	2.64			
	RHS												
	0.00	15.00	R/S	1	15.00			0.60	0.40	3.60			
	15.00	30.00	R/S	1	15.00			0.60	0.40	3.60			
	30.00	45.00	R/S	1	15.00			0.60	0.40	3.60			
	45.00	60.00	R/S	1	15.00			0.60	0.40	3.60			
	60.00	75.00	R/S	1	15.00			0.60	0.40	3.60			
	75.00	90.00	R/S	1	15.00			0.60	0.40	3.60			
	90.00	96.50	R/S	1	6.50			0.60	0.40	1.56			
	96.50	116.70	R/S	1	20.20			0.60	0.40	4.85			
	116.70	131.10	R/S	1	14.40			0.60	0.40	3.46			
	131.10	149.20	R/S	1	18.10			0.60	0.40	4.34			
	149.20	158.60	R/S	1	9.40			0.60	0.40	2.26			
	158.60	175.50	R/S	1	16.90			0.60	0.40	4.06			
	175.50	199.20	R/S	0	23.70			0.60	0.40	0.00	No Work		
	199.20	210.00	R/S	1	10.80			0.60	0.40	2.59			
	210.00	230.00	R/S	1	20.00			0.60	0.40	4.80			
	230.00	245.00	R/S	1	15.00			0.60	0.40	3.60			
	245.00	262.90	R/S	1	17.90			0.60	0.40	4.30			
	262.90	270.00	R/S	1	7.10			0.60	0.40	1.70			
	270.00	285.00	R/S	1	15.00			0.60	0.40	3.60			
	285.00	300.00	R/S	1	15.00			0.60	0.40	3.60			
	300.00	309.20	R/S	1	9.20			0.60	0.40	2.21			
	309.20	314.00	R/S	1	4.80			0.60	0.40	1.15			
	314.00	320.00	R/S	1	6.00			0.60	0.40	1.44			
	320.00	335.00	R/S	1	15.00			0.60	0.40	3.60			
	335.00	354.50	R/S	1	19.50			0.60	0.40	4.68			
	354.50	364.50	R/S	1	10.00			0.60	0.40	2.40			
	364.50	380.00	R/S	1	15.50			0.60	0.40	3.72			
	380.00	395.00	R/S	1	15.00			0.60	0.40	3.60			
	395.00	401.00	R/S	1	6.00			0.60	0.40	1.44			
	BDS Layout 4th cross Rd												
	LHS												
	0.00	26.40	L/S	1	26.40			0.60	0.40	6.34			
	26.40	47.60	L/S	1	21.20			0.60	0.40	5.09			
	47.60	60.00	L/S	1	12.40			0.60	0.40	2.98			
	60.00	75.00	L/S	1	15.00			0.60	0.40	3.60			
	75.00	90.00	L/S	1	15.00			0.60	0.40	3.60			
	90.00	103.50	L/S	1	13.50			0.60	0.40	3.24			
	103.50	106.50	L/S	1	3.00			0.60	0.40	0.72			
	106.50	108.50	L/S	1	2.00			0.60	0.40	0.48			

BOQ Item No	Description Chainage		Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit/ Remarks	Rate	Amount
	108.50	112.60	L/S	1	4.10			0.60	0.40	0.98			
	112.60	130.00	L/S	1	17.40			0.60	0.40	4.18			
	130.00	155.00	L/S	1	25.00			0.60	0.40	6.00			
	155.00	160.00	L/S	1	5.00			0.60	0.40	1.20			
	160.00	175.00	L/S	1	15.00			0.60	0.40	3.60			
	175.00	190.00	L/S	1	15.00			0.60	0.40	3.60			
	190.00	205.00	L/S	1	15.00			0.60	0.40	3.60			
	205.00	220.00	L/S	1	15.00			0.60	0.40	3.60			
	220.00	235.00	L/S	1	15.00			0.60	0.40	3.60			
	235.00	250.00	L/S	1	15.00			0.60	0.40	3.60			
	250.00	265.00	L/S	1	15.00			0.60	0.40	3.60			
	265.00	280.00	L/S	1	15.00			0.60	0.40	3.60			
	280.00	295.00	L/S	1	15.00			0.60	0.40	3.60			
	295.00	305.00	L/S	1	10.00			0.60	0.40	2.40			
	RHS												
	0.00	15.00	R/S	1	15.00			0.60	0.40	3.60			
	15.00	30.00	R/S	1	15.00			0.60	0.40	3.60			
	30.00	45.00	R/S	1	15.00			0.60	0.40	3.60			
	45.00	60.00	R/S	1	15.00			0.60	0.40	3.60			
	60.00	75.00	R/S	1	15.00			0.60	0.40	3.60			
	75.00	90.00	R/S	1	15.00			0.60	0.40	3.60			
	90.00	105.00	R/S	1	15.00			0.60	0.40	3.60			
	105.00	120.00	R/S	1	15.00			0.60	0.40	3.60			
	120.00	125.80	R/S	1	5.80			0.60	0.40	1.39			
	125.80	142.40	R/S	1	16.60			0.60	0.40	3.98			
	142.40	150.80	R/S	1	8.40			0.60	0.40	2.02			
	150.80	161.80	R/S	1	11.00			0.60	0.40	2.64			
	161.80	169.10	R/S	1	7.30			0.60	0.40	1.75			
	169.10	175.00	R/S	1	5.90			0.60	0.40	1.42			
	175.00	190.00	R/S	1	15.00			0.60	0.40	3.60			
	190.00	205.00	R/S	1	15.00			0.60	0.40	3.60			
	205.00	220.00	R/S	1	15.00			0.60	0.40	3.60			
	220.00	235.00	R/S	1	15.00			0.60	0.40	3.60			
	235.00	250.00	R/S	1	15.00			0.60	0.40	3.60			
	250.00	268.20	R/S	1	18.20			0.60	0.40	4.37			
	268.20	280.00	R/S	1	11.80			0.60	0.40	2.83			
	280.00	305.00	R/S	1	25.00			0.60	0.40	6.00			
	c/s b/w BDS Layout 4th and 3rd cross Rd												
	RHS												
	0.00	15.00	R/S	1	15.00			0.60	0.40	3.60			
	15.00	31.40	R/S	1	16.40			0.60	0.40	3.94			
	c/s b/w BDS Layout 3rd and 1st A cross Rd												
	LHS												
	0.00	15.00	L/S	1	15.00			0.60	0.40	3.60			
	15.00	30.00	L/S	1	15.00			0.60	0.40	3.60			
	30.00	45.00	L/S	1	15.00			0.60	0.40	3.60			
	45.00	61.00	L/S	1	16.00			0.60	0.40	3.84			
	61.00	67.80	L/S	0	6.80			0.60	0.40	0.00	c/s Rd No work		
	67.80	75.00	L/S	1	7.20			0.60	0.40	1.73			
	75.00	90.00	L/S	1	15.00			0.60	0.40	3.60			
	90.00	100.00	L/S	1	10.00			0.60	0.40	2.40			
	RHS												
	0.00	15.00	R/S	1	15.00			0.60	0.40	3.60			
	15.00	28.00	R/S	1	13.00			0.60	0.40	3.12			
	28.00	38.00	R/S	0	10.00			0.60	0.40	0.00	(No work Deck Slab)		
	38.00	47.70	R/S	1	9.70			0.60	0.40	2.33			
	47.70	61.00	R/S	1	13.30			0.60	0.40	3.19			
	61.00	74.00	R/S	1	13.00			0.60	0.40	3.12			
	74.00	85.00	R/S	1	11.00			0.60	0.40	2.64			
	85.00	100.00	R/S	1	15.00			0.60	0.40	3.60			
	Shiradi Sai Rathan Layout 2nd c/s road												
	1st c/s road												
	LHS												
	0.00	20.00	L/S	1	20.00			0.60	0.40	4.80			
	20.00	31.20	L/S	1	11.20			0.60	0.40	2.69			
	RHS												
	0.00	21.50	R/S	1	21.50			0.60	0.40	5.16			
	21.50	31.20	R/S	0	9.70			0.60	0.40	0.00	No Work		

BOQ Item No	Description Chainage		Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit/ Remarks	Rate	Amount
	2nd c/s road												
	LHS												
	0.00	15.00	L/S	1	15.00			0.60	0.40	3.60			
	15.00	38.60	L/S	1	23.60			0.60	0.40	5.66			
	RHS												
	0.00	15.00	R/S	1	15.00			0.60	0.40	3.60			
	15.00	38.60	R/S	1	23.60			0.60	0.40	5.66	No Work		
	3rd c/s road												
	LHS												
	0.00	10.00	L/S	1	10.00			0.60	0.40	2.40			
	10.00	19.50	L/S	1	9.50			0.60	0.40	2.28			
	Shiradi Sai Rathan Layout 3rd A c/s road												
	LHS												
	0.00	15.00	L/S	1	15.00			0.60	0.40	3.60			
	15.00	18.00	L/S	1	3.00			0.60	0.40	0.72			
	18.00	29.00	L/S	1	11.00			0.60	0.40	2.64			
	29.00	33.00	L/S	1	4.00			0.60	0.40	0.96			
	33.00	56.50	L/S	1	23.50			0.60	0.40	5.64			
	56.50	65.20	L/S	1	8.70			0.60	0.40	2.09			
	65.20	75.00	L/S	1	9.80			0.60	0.40	2.35			
	75.00	90.00	L/S	1	15.00			0.60	0.40	3.60			
	90.00	105.00	L/S	1	15.00			0.60	0.40	3.60			
	105.00	120.00	L/S	1	15.00			0.60	0.40	3.60			
	120.00	135.00	L/S	1	15.00			0.60	0.40	3.60			
	135.00	150.00	L/S	1	15.00			0.60	0.40	3.60			
	150.00	165.00	L/S	1	15.00			0.60	0.40	3.60			
	165.00	180.00	L/S	1	15.00			0.60	0.40	3.60			
	180.00	195.00	L/S	1	15.00			0.60	0.40	3.60			
	195.00	209.50	L/S	1	14.50			0.60	0.40	3.48			
	RHS												
	0.00	15.00	R/S	1	15.00			0.60	0.40	3.60			
	15.00	30.00	R/S	1	15.00			0.60	0.40	3.60			
	30.00	45.00	R/S	1	15.00			0.60	0.40	3.60			
	45.00	60.00	R/S	1	15.00			0.60	0.40	3.60			
	60.00	75.00	R/S	1	15.00			0.60	0.40	3.60			
	75.00	90.00	R/S	1	15.00			0.60	0.40	3.60			
	90.00	105.00	R/S	1	15.00			0.60	0.40	3.60			
	105.00	120.00	R/S	1	15.00			0.60	0.40	3.60			
	120.00	135.00	R/S	1	15.00			0.60	0.40	3.60			
	135.00	150.00	R/S	1	15.00			0.60	0.40	3.60			
	150.00	165.00	R/S	1	15.00			0.60	0.40	3.60			
	165.00	180.00	R/S	1	15.00			0.60	0.40	3.60			
	180.00	195.00	R/S	1	15.00			0.60	0.40	3.60			
	195.00	209.20	R/S	1	14.20			0.60	0.40	3.41			
	Shiradi Sai Rathan Layout 2nd A c/s road												
	LHS												
	0.00	19.00	L/S	1	19.00			0.60	0.40	4.56			
	19.00	22.00	L/S	1	3.00			0.60	0.40	0.72			
	22.00	28.30	L/S	1	6.30			0.60	0.40	1.51			
	28.30	32.00	L/S	1	3.70			0.60	0.40	0.89			
	32.00	42.00	L/S	1	10.00			0.60	0.40	2.40			
	42.00	50.00	L/S	0	8.00			0.60	0.40	0.00	No work		
	50.00	75.00	L/S	0	25.00			0.60	0.40	0.00	No work		
	75.00	86.00	L/S	0	11.00			0.60	0.40	0.00	No work		
	86.00	95.00	L/S	1	9.00			0.60	0.40	2.16			
	95.00	110.00	L/S	1	15.00			0.60	0.40	3.60			
	110.00	120.20	L/S	1	10.20			0.60	0.40	2.45			
	120.20	129.20	L/S	0	9.00			0.60	0.40	0.00	No work		
	129.20	140.00	L/S	0	10.80			0.60	0.40	0.00	No work		
	140.00	150.00	L/S	0	10.00			0.60	0.40	0.00	No work		
	150.00	160.00	L/S	0	10.00			0.60	0.40	0.00	No work		
	160.00	170.00	L/S	1	10.00			0.60	0.40	2.40			
	170.00	185.00	L/S	1	15.00			0.60	0.40	3.60			
	185.00	200.00	L/S	1	15.00			0.60	0.40	3.60			
	200.00	210.00	L/S	1	10.00			0.60	0.40	2.40			
	210.00	222.00	L/S	1	12.00			0.60	0.40	2.88			
	RHS												
	0.00	22.80	R/S	1	22.80			0.60	0.40	5.47			
	22.80	28.30	R/S	1	5.50			0.60	0.40	1.32			
	28.30	32.00	R/S	1	3.70			0.60	0.40	0.89			

BOQ Item No	Description Chainage		Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit/ Remarks	Rate	Amount
	32.00	38.40	R/S	1	6.40			0.60	0.40	1.54			
	38.40	41.40	R/S	1	3.00			0.60	0.40	0.72			
	41.40	50.00	R/S	1	8.60			0.60	0.40	2.06			
	50.00	65.00	R/S	1	15.00			0.60	0.40	3.60			
	65.00	80.00	R/S	1	15.00			0.60	0.40	3.60			
	80.00	95.00	R/S	1	15.00			0.60	0.40	3.60			
	95.00	110.00	R/S	1	15.00			0.60	0.40	3.60			
	110.00	120.20	R/S	1	10.20			0.60	0.40	2.45			
	120.20	129.50	R/S	1	9.30			0.60	0.40	2.23			
	129.50	145.00	R/S	0	15.50			0.60	0.40	0.00	No work		
	145.00	160.00	R/S	0	15.00			0.60	0.40	0.00	No work		
	160.00	175.00	R/S	1	15.00			0.60	0.40	3.60			
	175.00	190.00	R/S	1	15.00			0.60	0.40	3.60			
	190.00	203.10	R/S	1	13.10			0.60	0.40	3.14			
	203.10	222.00	R/S	1	18.90			0.60	0.40	4.54			
	Shiradi Sai Rathan Layout 1st A c/s road												
	LHS												
	0.00	10.00	L/S	1	10.00			0.60	0.40	2.40	Open BS drain		
	10.00	22.20	L/S	1	12.20			0.60	0.40	2.93	only desilt(Home entrance)		
	22.20	36.30	L/S	1	14.10			0.60	0.40	3.38	Open BS drain		
	36.30	46.00	L/S	1	9.70			0.60	0.40	2.33	only desilt (Home entrance)		
	46.00	49.00	L/S	1	3.00			0.60	0.40	0.72	only desilt(open drain)		
	49.00	54.00	L/S	1	5.00			0.60	0.40	1.20	Only Desilt		
	54.00	55.50	L/S	1	1.50			0.60	0.40	0.36	Only Desilt		
	55.50	64.50	L/S	1	9.00			0.60	0.40	2.16	Only Desilt		
	64.50	68.50	L/S	1	4.00			0.60	0.40	0.96	only desilt (Home entrance)		
	68.50	83.00	L/S	1	14.50			0.60	0.40	3.48	Desilt+RR		
	83.00	92.00	L/S	1	9.00			0.60	0.40	2.16	Desilt+RR		
	92.00	105.00	L/S	1	13.00			0.60	0.40	3.12	Only desilt		
	105.00	123.00	L/S	1	18.00			0.60	0.40	4.32	Only desilt		
	123.00	141.50	L/S	0	18.50			0.60	0.40	0.00	No work(Home entrance)		
	141.50	166.00	L/S	1	24.50			0.60	0.40	5.88	Desilt+RR		
	166.00	190.00	L/S	1	24.00			0.60	0.40	5.76	Open drain desilt		
	190.00	203.00	L/S	0	13.00			0.60	0.40	0.00	No work		
	203.00	225.00	L/S	1	22.00			0.60	0.40	5.28	Open drain desilt		
	225.00	246.60	L/S	0	21.60			0.60	0.40	0.00	No work		
	RHS												
	0.00	5.00	R/S	1	5.00			0.60	0.40	1.20	Only desilt		
	5.00	10.00	R/S	1	5.00			0.60	0.40	1.20	Desilt+RR		
	10.00	19.50	R/S	0	9.50			0.60	0.40	0.00	No work		
	19.50	35.50	R/S	1	16.00			0.60	0.40	3.84	Desilt+RR		
	35.50	47.00	R/S	1	11.50			0.60	0.40	2.76	Only desilt		
	47.00	51.00	R/S	1	4.00			0.60	0.40	0.96	Desilt+RR		
	51.00	78.50	R/S	1	27.50			0.60	0.40	6.60	Open drain desilt		
	78.50	100.00	R/S	0	21.50			0.60	0.40	0.00	No work(Home entrance)		
	100.00	120.00	R/S	0	20.00			0.60	0.40	0.00	No work(Home entrance)		
	120.00	135.00	R/S	1	15.00			0.60	0.40	3.60	Desilt+RR		
	135.00	150.00	R/S	1	15.00			0.60	0.40	3.60	Desilt+RR		
	150.00	158.50	R/S	1	8.50			0.60	0.40	2.04	Desilt+RR		
	158.50	185.30	R/S	0	26.80			0.60	0.40	0.00	No work(Home entrance)		
	185.30	194.30	R/S	1	9.00			0.60	0.40	2.16	only desilt (Home entrance)		
	194.30	218.50	R/S	1	24.20			0.60	0.40	5.81	Open drain desilt		
	218.50	232.00	R/S	1	13.50			0.60	0.40	3.24	Only desilt		
	232.00	246.60	R/S	0	14.60			0.60	0.40	0.00	No work		
	Shiradi Sai Rathan Layout Dead end road												
	LHS												
	0.00	15.00	L/S	1	15.00			0.60	0.40	3.60			
	15.00	30.00	L/S	1	15.00			0.60	0.40	3.60			
	30.00	45.00	L/S	0	15.00			0.60	0.40	0.00	No work		
	45.00	69.00	L/S	0	24.00			0.60	0.40	0.00	No work		

BOQ Item No	Description Chainage		Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit/ Remarks	Rate	Amount
	B. Ramaiah Rd(Hegdenagar Main Rd)												
	LHS												
	0.00	10.40	L/S	0	10.40			0.60	0.40	0.00	No drain (c/s Rd St.Teresa clg of Pharmacy)		
	10.40	41.20	L/S	1	30.80			0.60	0.40	7.39			
	41.20	49.50	L/S	1	8.30			0.60	0.40	1.99	c/s Rd shaktinagar(Anjaneya Temple Rd)		
	49.50	71.00	L/S	1	21.50			0.60	0.40	5.16			
	71.00	85.00	L/S	0	14.00			0.60	0.40	0.00	Buildings Smart ADDS, SS Deccor(No Work)		
	85.00	100.00	L/S	0	15.00			0.60	0.40	0.00			
	100.00	115.00	L/S	0	15.00			0.60	0.40	0.00			
	115.00	131.00	L/S	0	16.00			0.60	0.40	0.00			
	131.00	158.00	L/S	1	27.00			0.60	0.40	6.48			
	158.00	171.50	L/S	0	13.50			0.60	0.40	0.00	No Work(Commercial buildings)		
	171.50	189.50	L/S	1	18.00			0.60	0.40	4.32			
	189.50	202.50	L/S	1	13.00			0.60	0.40	3.12			
	202.50	209.00	L/S	1	6.50			0.60	0.40	1.56			
	209.00	238.50	L/S	1	29.50			0.60	0.40	7.08			
	238.50	247.50	L/S	1	9.00			0.60	0.40	2.16	Only Desilt		
	247.50	255.50	L/S	1	8.00			0.60	0.40	1.92			
	255.50	277.00	L/S	1	21.50			0.60	0.40	5.16			
	277.00	286.50	L/S	1	9.50			0.60	0.40	2.28			
	286.50	300.00	L/S	1	13.50			0.60	0.40	3.24			
	300.00	314.00	L/S	1	14.00			0.60	0.40	3.36			
	314.00	322.00	L/S	1	8.00			0.60	0.40	1.92	c/s Rd(only Desilt)		
	322.00	331.50	L/S	1	9.50			0.60	0.40	2.28			
	331.50	353.50	L/S	1	22.00			0.60	0.40	5.28			
	353.50	361.30	L/S	1	7.80			0.60	0.40	1.87	c/s Rd(Deck slab)desilt		
	361.30	373.50	L/S	1	12.20			0.60	0.40	2.93			
	373.50	386.00	L/S	1	12.50			0.60	0.40	3.00			
	386.00	393.00	L/S	1	7.00			0.60	0.40	1.68	c/s Rd (Culvert Desilt)		
	393.00	419.00	L/S	1	26.00			0.60	0.40	6.24			
	419.00	425.50	L/S	1	6.50			0.60	0.40	1.56	c/s Rd (Culvert Desilt)		
	425.50	451.00	L/S	1	25.50			0.60	0.40	6.12			
	451.00	458.00	L/S	1	7.00			0.60	0.40	1.68			
	458.00	470.00	L/S	0	12.00			0.60	0.40	0.00	No work(c/s Rd)		
	470.00	504.50	L/S	1	34.50			0.60	0.40	8.28			
	504.50	511.00	L/S	0	6.50			0.60	0.40	0.00	No work(c/s Rd)		
	511.00	544.00	L/S	1	33.00			0.60	0.40	7.92			
	544.00	550.00	L/S	1	6.00			0.60	0.40	1.44	c/s Rd (Culvert Desilt)		
	550.00	583.50	L/S	1	33.50			0.60	0.40	8.04			
	RHS												
	0.00	7.50	R/S	1	7.50			0.60	0.40	1.80			
	7.50	14.00	R/S	0	6.50			0.60	0.40	0.00	No work(Deck Slab)		
	14.00	30.00	R/S	1	16.00			0.60	0.40	3.84			
	30.00	45.00	R/S	1	15.00			0.60	0.40	3.60			
	45.00	52.50	R/S	0	7.50			0.60	0.40	0.00	No work(1st Mn 14th c/s Hegdenagar)		
	52.50	70.00	R/S	1	17.50			0.60	0.40	4.20			
	70.00	85.50	R/S	1	15.50			0.60	0.40	3.72			
	85.50	93.00	R/S	0	7.50			0.60	0.40	0.00	No work(c/s Rd)		
	93.00	105.00	R/S	1	12.00			0.60	0.40	2.88			
	105.00	125.50	R/S	1	20.50			0.60	0.40	4.92			
	125.50	133.00	R/S	0	7.50			0.60	0.40	0.00	No work Deck slab(1st Mn 12th c/s Hegdenagar)		
	133.00	141.00	R/S	1	8.00			0.60	0.40	1.92			
	141.00	156.00	R/S	0	15.00			0.60	0.40	0.00	No work		
	156.00	163.70	R/S	1	7.70			0.60	0.40	1.85			
	163.70	172.60	R/S	0	8.90			0.60	0.40	0.00	No work(c/s Rd)		
	172.60	204.00	R/S	0	31.40			0.60	0.40	0.00	No work(drain present Closed area)		
	204.00	213.00	R/S	0	9.00			0.60	0.40	0.00	c/s rd(No wrk) deck slab		

BOQ Item No	Description Chainage		Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit/ Remarks	Rate	Amount
	213.00	243.00	R/S	1	30.00			0.60	0.40	7.20			
	243.00	252.40	R/S	0	9.40			0.60	0.40	0.00	New Culvert (c/s Rd)		
	252.40	267.60	R/S	1	15.20			0.60	0.40	3.65			
	267.60	283.50	R/S	1	15.90			0.60	0.40	3.82			
	283.50	292.50	R/S	0	9.00			0.60	0.40	0.00	New Culvert (c/s Rd)		
	292.50	302.00	R/S	1	9.50			0.60	0.40	2.28			
	302.00	323.00	R/S	0	21.00			0.60	0.40	0.00	No work		
	323.00	332.40	R/S	0	9.40			0.60	0.40	0.00	New Culvert (c/s Rd)		
	332.40	342.00	R/S	1	9.60			0.60	0.40	2.30			
	342.00	348.00	R/S	1	6.00			0.60	0.40	1.44			
	348.00	362.00	R/S	1	14.00			0.60	0.40	3.36			
	362.00	371.00	R/S	0	9.00			0.60	0.40	0.00	New Culvert (c/s Rd)		
	371.00	380.00	R/S	1	9.00			0.60	0.40	2.16			
	380.00	395.00	R/S	1	15.00			0.60	0.40	3.60			
	395.00	401.50	R/S	1	6.50			0.60	0.40	1.56			
	401.50	408.00	R/S	1	6.50			0.60	0.40	1.56	Old Culvert Desilt		
	408.00	427.20	R/S	1	19.20			0.60	0.40	4.61			
	427.20	435.00	R/S	1	7.80			0.60	0.40	1.87	c/s Rd old Culvert Desilt		
	435.00	466.50	R/S	1	31.50			0.60	0.40	7.56			
	466.50	474.00	R/S	1	7.50			0.60	0.40	1.80	c/s Rd(Culvert Desilt)		
	474.00	490.00	R/S	1	16.00			0.60	0.40	3.84			
	490.00	506.00	R/S	1	16.00			0.60	0.40	3.84			
	506.00	513.50	R/S	1	7.50			0.60	0.40	1.80	c/s rd(Culvert Desilt)		
	513.50	530.00	R/S	1	16.50			0.60	0.40	3.96			
	530.00	543.60	R/S	1	13.60			0.60	0.40	3.26			
	543.60	552.80	R/S	1	9.20			0.60	0.40	2.21	1st Mn 1st c/s Culvert Desilt		
	552.80	570.00	R/S	1	17.20			0.60	0.40	4.13			
	570.00	583.50	R/S	1	13.50			0.60	0.40	3.24			
	Apoorva Enclave												
	LHS												
	0.00	15.00	L/S	1	15.00			0.60	0.40	3.60	Open Drain		
	15.00	30.00	L/S	1	15.00			0.60	0.40	3.60	Open Drain		
	30.00	45.00	L/S	1	15.00			0.60	0.40	3.60	Open Drain		
	45.00	60.00	L/S	1	15.00			0.60	0.40	3.60	Open Drain		
	60.00	75.00	L/S	1	15.00			0.60	0.40	3.60	Open Drain		
	75.00	83.10	L/S	1	8.10			0.60	0.40	1.94	Open Drain		
	83.10	92.00	L/S	1	8.90			0.60	0.40	2.14	1.2 BS slab		
	92.00	107.00	L/S	1	15.00			0.60	0.40	3.60	Open Drain		
	107.00	122.00	L/S	1	15.00			0.60	0.40	3.60	Open Drain		
	122.00	137.00	L/S	1	15.00			0.60	0.40	3.60	Open Drain		
	137.00	152.00	L/S	1	15.00			0.60	0.40	3.60	Open Drain		
	152.00	167.00	L/S	1	15.00			0.60	0.40	3.60	Open Drain		
	167.00	182.00	L/S	1	15.00			0.60	0.40	3.60	Open Drain		
	182.00	197.00	L/S	1	15.00			0.60	0.40	3.60	Open Drain		
	197.00	212.00	L/S	1	15.00			0.60	0.40	3.60	Open Drain		
	212.00	231.00	L/S	1	19.00			0.60	0.40	4.56	Open Drain		
	231.00	240.00	L/S	0	9.00			0.60	0.40	0.00	No Work		
	240.00	255.00	L/S	1	15.00			0.60	0.40	3.60	Open Drain		
	255.00	270.00	L/S	1	15.00			0.60	0.40	3.60	Open Drain		
	270.00	285.00	L/S	1	15.00			0.60	0.40	3.60	Open Drain		
	285.00	300.00	L/S	1	15.00			0.60	0.40	3.60	Open Drain		
	300.00	315.00	L/S	1	15.00			0.60	0.40	3.60	Open Drain		
	315.00	330.00	L/S	1	15.00			0.60	0.40	3.60	Open Drain		
	330.00	345.00	L/S	1	15.00			0.60	0.40	3.60	Open Drain		
	345.00	360.00	L/S	1	15.00			0.60	0.40	3.60	Open Drain		
	360.00	375.00	L/S	1	15.00			0.60	0.40	3.60	Open Drain		
	375.00	390.00	L/S	1	15.00			0.60	0.40	3.60	Open Drain		
	390.00	405.00	L/S	1	15.00			0.60	0.40	3.60	Open Drain		
	405.00	420.00	L/S	1	15.00			0.60	0.40	3.60	Open Drain		
	420.00	435.00	L/S	1	15.00			0.60	0.40	3.60	Open Drain		
	435.00	443.00	L/S	1	8.00			0.60	0.40	1.92	Open Drain		
	443.00	445.50	L/S	0	2.50			0.60	0.40	0.00	No Work		
	445.50	460.50	L/S	1	15.00			0.60	0.40	3.60	Open Drain		
	460.50	475.50	L/S	1	15.00			0.60	0.40	3.60	Open Drain		
	475.50	490.50	L/S	1	15.00			0.60	0.40	3.60	Open Drain		

BOQ Item No	Description		Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit/ Remarks	Rate	Amount
	Chainage												
	490.50	505.50	L/S	1	15.00			0.60	0.40	3.60	Open Drain		
	505.50	520.50	L/S	1	15.00			0.60	0.40	3.60	Open Drain		
	520.50	530.50	L/S	1	10.00			0.60	0.40	2.40	Open Drain		
	RHS												
	0.00	15.00	R/S	1	15.00			0.60	0.40	3.60	Open Drain		
	15.00	30.00	R/S	1	15.00			0.60	0.40	3.60	Open Drain		
	30.00	45.00	R/S	1	15.00			0.60	0.40	3.60	Open Drain		
	45.00	60.00	R/S	1	15.00			0.60	0.40	3.60	Open Drain		
	60.00	75.00	R/S	1	15.00			0.60	0.40	3.60	Open Drain		
	75.00	90.00	R/S	1	15.00			0.60	0.40	3.60	Open Drain		
	90.00	105.00	R/S	1	15.00			0.60	0.40	3.60	Open Drain		
	105.00	120.00	R/S	1	15.00			0.60	0.40	3.60	Open Drain		
	120.00	135.00	R/S	1	15.00			0.60	0.40	3.60	Open Drain		
	135.00	150.00	R/S	1	15.00			0.60	0.40	3.60	Open Drain		
	150.00	165.00	R/S	1	15.00			0.60	0.40	3.60	Open Drain		
	165.00	180.00	R/S	1	15.00			0.60	0.40	3.60	Open Drain		
	180.00	195.00	R/S	1	15.00			0.60	0.40	3.60	Open Drain		
	195.00	210.00	R/S	1	15.00			0.60	0.40	3.60	Open Drain		
	210.00	225.00	R/S	1	15.00			0.60	0.40	3.60	Open Drain		
	225.00	240.00	R/S	1	15.00			0.60	0.40	3.60	Open Drain		
	240.00	255.00	R/S	1	15.00			0.60	0.40	3.60	Open Drain		
	255.00	270.00	R/S	1	15.00			0.60	0.40	3.60	Open Drain		
	270.00	285.00	R/S	1	15.00			0.60	0.40	3.60	Open Drain		
	285.00	300.00	R/S	1	15.00			0.60	0.40	3.60	Open Drain		
	300.00	315.00	R/S	1	15.00			0.60	0.40	3.60	Open Drain		
	315.00	330.00	R/S	1	15.00			0.60	0.40	3.60	Open Drain		
	330.00	345.00	R/S	1	15.00			0.60	0.40	3.60	Open Drain		
	345.00	360.00	R/S	1	15.00			0.60	0.40	3.60	Open Drain		
	360.00	375.00	R/S	1	15.00			0.60	0.40	3.60	Open Drain		
	375.00	390.00	R/S	1	15.00			0.60	0.40	3.60	Open Drain		
	390.00	405.00	R/S	1	15.00			0.60	0.40	3.60	Open Drain		
	405.00	413.00	R/S	1	8.00			0.60	0.40	1.92	Open Drain		
	413.00	420.60	R/S	1	7.60			0.60	0.40	1.82	1.2 BS slab		
	420.60	435.00	R/S	1	14.40			0.60	0.40	3.46	Open Drain		
	435.00	450.00	R/S	1	15.00			0.60	0.40	3.60	Open Drain		
	450.00	465.00	R/S	1	15.00			0.60	0.40	3.60	Open Drain		
	465.00	480.00	R/S	1	15.00			0.60	0.40	3.60	Open Drain		
	480.00	495.00	R/S	1	15.00			0.60	0.40	3.60	Open Drain		
	495.00	510.00	R/S	1	15.00			0.60	0.40	3.60	Open Drain		
	510.00	522.50	R/S	1	12.50			0.60	0.40	3.00	Open Drain		
	522.50	530.50	R/S	0	8.00			0.60	0.40	0.00	c/s Rd(No drain)		
	BS drain Desilt												
	Shirdi Sai Rathan Layout												
	2nd Cross Rd												
	LHS												
	0.00	9.00	L/S	1	9.00			0.50	0.45	2.03	Open drain		
	9.00	25.00	L/S	0	16.00			0.50	0.45	0.00	No work		
	25.00	34.00	L/S	0	9.00			0.50	0.45	0.00	No work		
	34.00	50.00	L/S	1	16.00			0.50	0.45	3.60	Open drain		
	50.00	65.00	L/S	1	15.00			0.50	0.45	3.38	Open drain		
	65.00	82.50	L/S	1	17.50			0.50	0.45	3.94	Open drain		
	82.50	95.00	L/S	0	12.50			0.50	0.45	0.00	No work		
	95.00	106.00	L/S	0	11.00			0.50	0.45	0.00	No work		
	106.00	110.30	L/S	1	4.30			0.50	0.45	0.97	1.2 bs		
	110.30	121.20	L/S	1	10.90			0.50	0.45	2.45	0.9 bs		
	RHS												
	0.00	10.00	R/S	1	10.00			0.50	0.45	2.25	Open drain		
	10.00	24.20	R/S	1	14.20			0.50	0.45	3.20	Open drain		
	24.20	30.00	R/S	0	5.80			0.50	0.45	0.00	No work		
	30.00	43.50	R/S	1	13.50			0.50	0.45	3.04	1.2 bs		
	43.50	47.50	R/S	1	4.00			0.50	0.45	0.90	0.9 bs		
	47.50	56.00	R/S	1	8.50			0.50	0.45	1.91	Open drain		
	56.00	63.50	R/S	0	7.50			0.50	0.45	0.00	C/S Road		
	63.50	70.00	R/S	0	6.50			0.50	0.45	0.00	No work		
	70.00	88.20	R/S	1	18.20			0.50	0.45	4.10	Open drain		
	88.20	94.50	R/S	0	6.30			0.50	0.45	0.00	C/S Road		
	94.50	110.00	R/S	1	15.50			0.50	0.45	3.49	Open drain		
	110.00	120.50	R/S	1	10.50			0.50	0.45	2.36	Open drain		
	Connected to 2nd A ,B and 1st Cross Road												
	LHS												
	0.00	15.00	L/S	1	15.00			0.50	0.45	3.38	Open drain		
	15.00	30.00	L/S	1	15.00			0.50	0.45	3.38	Open drain		

BOQ Item No	Description Chainage		Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit/ Remarks	Rate	Amount
	30.00	44.00	L/S	1	14.00			0.50	0.45	3.15	Open drain		
	44.00	51.50	L/S	0	7.50			0.50	0.45	0.00	C/S Road		
	51.50	67.50	L/S	1	16.00			0.50	0.45	3.60	0.9 bs		
	67.50	71.20	L/S	1	3.70			0.50	0.45	0.83	1.2 bs		
	71.20	78.00	L/S	1	6.80			0.50	0.45	1.53	Open drain		
	78.00	90.80	L/S	1	12.80			0.50	0.45	2.88	0.9 bs		
	90.80	97.80	L/S	0	7.00			0.50	0.45	0.00	C/S Road		
	97.80	104.50	L/S	1	6.70			0.50	0.45	1.51	Open drain		
	RHS												
	0.00	8.50	R/S	0	8.50			0.50	0.45	0.00	No work		
	8.50	29.80	R/S	1	21.30			0.50	0.45	4.79	Open drain		
	29.80	36.30	R/S	0	6.50			0.50	0.45	0.00	C/S Road		
	36.30	50.00	R/S	1	13.70			0.50	0.45	3.08	Open drain		
	50.00	62.80	R/S	1	12.80			0.50	0.45	2.88	Open drain		
	62.80	70.20	R/S	0	7.40			0.50	0.45	0.00	C/S Road		
	70.20	85.00	R/S	1	14.80			0.50	0.45	3.33	Open drain		
	85.00	96.50	R/S	1	11.50			0.50	0.45	2.59	Open drain		
	96.50	102.80	R/S	0	6.30			0.50	0.45	0.00	C/S Road		
	1st Cross Road												
	LHS												
	0.00	15.00	L/S	1	15.00			0.50	0.45	3.38	Open drain		
	15.00	30.00	L/S	1	15.00			0.50	0.45	3.38	Open drain		
	30.00	45.00	L/S	1	15.00			0.50	0.45	3.38	Open drain		
	45.00	60.00	L/S	1	15.00			0.50	0.45	3.38	Open drain		
	60.00	75.00	L/S	1	15.00			0.50	0.45	3.38	Open drain		
	75.00	90.00	L/S	1	15.00			0.50	0.45	3.38	Open drain		
	90.00	105.00	L/S	1	15.00			0.50	0.45	3.38	Open drain		
	105.00	111.00	L/S	1	6.00			0.50	0.45	1.35	Open drain		
	111.00	123.00	L/S	1	12.00			0.50	0.45	2.70	Disilt only		
	123.00	132.00	L/S	1	9.00			0.50	0.45	2.03	0.9 bs		
	132.00	136.60	L/S	1	4.60			0.50	0.45	1.04	Open drain		
	RHS												
	0.00	15.00	R/S	0	15.00			0.50	0.45	0.00	No work		
	15.00	32.00	R/S	0	17.00			0.50	0.45	0.00	No work		
	32.00	45.00	R/S	1	13.00			0.50	0.45	2.93	Open drain		
	45.00	60.00	R/S	1	15.00			0.50	0.45	3.38	Open drain		
	60.00	75.00	R/S	1	15.00			0.50	0.45	3.38	Open drain		
	75.00	90.00	R/S	1	15.00			0.50	0.45	3.38	Open drain		
	90.00	105.00	R/S	1	15.00			0.50	0.45	3.38	Open drain		
	105.00	111.70	R/S	1	6.70			0.50	0.45	1.51	Open drain		
	111.70	123.00	R/S	1	11.30			0.50	0.45	2.54	0.9 bs		
	123.00	132.00	R/S	1	9.00			0.50	0.45	2.03	0.9 bs		
	132.00	136.60	R/S	1	4.60			0.50	0.45	1.04	0.9 bs		
	BDS Layout 2nd 'A' c/s Rd(Dr.Shivarama Karanth nagar Mn to GKVK Double Rd)												
	LHS												
	0.00	9.00	L/S	0	9.00			0.50	0.45	0.00	No Work		
	9.00	28.00	L/S	1	19.00			0.50	0.45	4.28	Desilt only		
	28.00	37.50	L/S	1	9.50			0.50	0.45	2.14	Open drain		
	37.50	46.00	L/S	0	8.50			0.50	0.45	0.00	c/s Rd No work		
	46.00	72.00	L/S	1	26.00			0.50	0.45	5.85	Open drain		
	RHS												
	0.00	1.00	R/S	0	1.00			0.50	0.45	0.00	No drain		
	1.00	23.00	R/S	1	22.00			0.50	0.45	4.95	Desilt only		
	23.00	32.20	R/S	1	9.20			0.50	0.45	2.07	Open drain		
	32.20	45.70	R/S	1	13.50			0.50	0.45	3.04	Desilt only		
	45.70	53.50	R/S	0	7.80			0.50	0.45	0.00	No work		
	53.50	57.00	R/S	1	3.50			0.50	0.45	0.79	Desilt only		
	57.00	72.00	R/S	1	15.00			0.50	0.45	3.38	Open drain		
	BDS Layout 2nd c/s Rd(Dr.Shivarama Karanth ngar Mn to Amanthrana Party Hall)												
	LHS												
	0.00	15.00	L/S	1	15.00			0.50	0.45	3.38	Open drain		
	15.00	30.00	L/S	1	15.00			0.50	0.45	3.38	Open drain		
	30.00	41.00	L/S	1	11.00			0.50	0.45	2.48	Open drain		
	41.00	58.00	L/S	0	17.00			0.50	0.45	0.00	No work		
	58.00	83.70	L/S	1	25.70			0.50	0.45	5.78	Open drain		
	RHS												
	0.00	26.00	R/S	1	26.00			0.50	0.45	5.85	Open drain		
	26.00	30.50	R/S	0	4.50			0.50	0.45	0.00	No work		
	30.50	55.50	R/S	1	25.00			0.50	0.45	5.63	Open drain		
	55.50	83.70	R/S	1	28.20			0.50	0.45	6.35	Desilt only		

BOQ Item No	Description Chainage		Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit/ Remarks	Rate	Amount
	BDS Layout 1st c/s Rd(Dr.Shivarama Karanth ngar Mn to GKVK Double Rd)												
	LHS												
	0.00	64.00	L/S	0	64.00			0.50	0.45	0.00	No work		
	64.00	80.00	L/S	1	16.00			0.50	0.45	3.60	Open drain		
	80.00	102.20	L/S	0	22.20			0.50	0.45	0.00	No work		
	Hegdenagar												
	1st Cross Road (GKVK Double Rd to RKH 2nd Mn Rd)												
	LHS												
	0.00	15.00	L/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	15.00	30.00	L/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	30.00	41.00	L/S	1	11.00			0.50	0.50	2.75	0.9 PCS		
	41.00	49.00	L/S	1	8.00			0.50	0.50	2.00	0.9 BS slab		
	49.00	60.00	L/S	1	11.00			0.50	0.50	2.75	0.9 PCS		
	60.00	75.00	L/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	75.00	90.00	L/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	90.00	105.00	L/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	105.00	120.00	L/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	120.00	135.00	L/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	135.00	156.00	L/S	1	21.00			0.50	0.50	5.25	0.9 PCS		
	156.00	161.50	L/S	1	5.50			0.50	0.50	1.38	Only desilt		
	161.50	174.00	L/S	1	12.50			0.50	0.50	3.13	No work		
	174.00	193.00	L/S	1	19.00			0.50	0.50	4.75	0.9 PCS		
	193.00	202.00	L/S	0	9.00			0.50	0.50	0.00	No work		
	202.00	212.00	L/S	1	10.00			0.50	0.50	2.50	0.9 PCS		
	212.00	221.00	L/S	1	9.00			0.50	0.50	2.25	0.9 BS slab		
	221.00	240.50	L/S	1	19.50			0.50	0.50	4.88	Only desilt		
	240.50	253.30	L/S	0	12.80			0.50	0.50	0.00	No work		
	RHS												
	0.00	15.00	R/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	15.00	30.00	R/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	30.00	45.00	R/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	45.00	60.00	R/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	60.00	75.00	R/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	75.00	90.00	R/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	90.00	105.00	R/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	105.00	120.00	R/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	120.00	135.00	R/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	135.00	150.00	R/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	150.00	165.00	R/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	165.00	180.00	R/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	180.00	195.00	R/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	195.00	210.00	R/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	210.00	225.00	R/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	225.00	240.00	R/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	240.00	249.00	R/S	1	9.00			0.50	0.50	2.25	0.9 PCS		
	249.00	253.30	R/S	0	4.30			0.50	0.50	0.00	No work		
	2nd Cross Road (GKVK Double Rd to RKH 2nd Mn Rd)												
	LHS												
	0.00	2.00	L/S	0	2.00			0.50	0.50	0.00	No drain		
	2.00	14.00	L/S	1	12.00			0.50	0.50	3.00	0.9 PCS		
	14.00	25.00	L/S	0	11.00			0.50	0.50	0.00	No work		
	25.00	30.00	L/S	1	5.00			0.50	0.50	1.25	0.9 BS slab		
	30.00	45.00	L/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	45.00	60.00	L/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	60.00	75.00	L/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	75.00	90.00	L/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	90.00	105.00	L/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	105.00	128.00	L/S	1	23.00			0.50	0.50	5.75	0.9 PCS		
	128.00	135.00	L/S	1	7.00			0.50	0.50	1.75	Only desilt		
	135.00	141.00	L/S	1	6.00			0.50	0.50	1.50	Only desilt		
	141.00	150.00	L/S	1	9.00			0.50	0.50	2.25	0.9 PCS		
	150.00	165.00	L/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	165.00	180.00	L/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	180.00	195.00	L/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	195.00	210.00	L/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	210.00	237.00	L/S	0	27.00			0.50	0.50	3.75	0.9 PCS		
	237.00	246.00	L/S	1	9.00			0.50	0.50	0.00	No work		
	RHS												
	0.00	2.00	R/S	0	2.00			0.50	0.50	2.25	0.9 PCS		
	2.00	15.00	R/S	1	13.00			0.50	0.50	0.00	No drain		
	15.00	30.00	R/S	1	15.00			0.50	0.50	3.25	0.9 PCS		
	30.00	57.00	R/S	1	27.00			0.50	0.50	3.75	0.9 PCS		
								0.50	0.50	6.75	only desilt		

BOQ Item No	Description Chainage		Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit/ Remarks	Rate	Amount
	57.00	65.00	R/S	0	8.00			0.50	0.50	0.00	No work		
	65.00	74.00	R/S	1	9.00			0.50	0.50	2.25	0.9 PCS		
	74.00	87.00	R/S	0	13.00			0.50	0.50	0.00	No work		
	87.00	109.00	R/S	1	22.00			0.50	0.50	5.50	0.9 PCS		
	109.00	114.00	R/S	0	5.00			0.50	0.50	0.00	No work		
	114.00	130.00	R/S	1	16.00			0.50	0.50	4.00	0.9 PCS		
	130.00	155.50	R/S	1	25.50			0.50	0.50	6.38	0.9 PCS		
	155.50	175.00	R/S	0	19.50			0.50	0.50	0.00	No work		
	175.00	190.00	R/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	190.00	205.00	R/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	205.00	220.00	R/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	220.00	239.00	R/S	1	19.00			0.50	0.50	4.75	0.9 PCS		
	239.00	246.00	R/S	1	7.00			0.50	0.50	1.75	only desilt		
	3rd Cross Road (GKVK Double Rd to RKH 2nd Mn Rd)												
	LHS												
	0.00	2.00	L/S	0	2.00			0.50	0.50	0.00	No drain		
	2.00	15.00	L/S	1	13.00			0.50	0.50	3.25	0.9 PCS		
	15.00	30.00	L/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	30.00	46.00	L/S	1	16.00			0.50	0.50	4.00	0.9 PCS		
	46.00	64.70	L/S	1	18.70			0.50	0.50	4.68	Only desilt		
	64.70	90.00	L/S	1	25.30			0.50	0.50	6.33	0.9 PCS		
	90.00	108.00	L/S	1	18.00			0.50	0.50	4.50	Only desilt		
	108.00	115.00	L/S	1	7.00			0.50	0.50	1.75	0.9 PCS		
	115.00	130.00	L/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	130.00	145.00	L/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	145.00	160.00	L/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	160.00	175.00	L/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	175.00	195.00	L/S	1	20.00			0.50	0.50	5.00	0.9 PCS		
	195.00	210.00	L/S	1	15.00			0.50	0.50	3.75	Only desilt		
	210.00	225.00	L/S	1	15.00			0.50	0.50	3.75	Only desilt		
	225.00	241.00	L/S	1	16.00			0.50	0.50	4.00	0.9 PCS		
	RHS												
	0.00	2.00	R/S	0	2.00			0.50	0.50	0.00	No drain		
	2.00	15.00	R/S	1	13.00			0.50	0.50	3.25	0.9 PCS		
	15.00	30.00	R/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	30.00	45.00	R/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	45.00	67.50	R/S	1	22.50			0.50	0.50	5.63	0.9 PCS		
	67.50	72.50	R/S	1	5.00			0.50	0.50	1.25	1.2 BS		
	72.50	84.00	R/S	1	11.50			0.50	0.50	2.88	Only desilt		
	84.00	107.00	R/S	1	23.00			0.50	0.50	5.75	0.9 PCS		
	107.00	120.00	R/S	0	13.00			0.50	0.50	0.00	No work		
	120.00	133.00	R/S	1	13.00			0.50	0.50	3.25	0.9 PCS		
	133.00	154.00	R/S	0	21.00			0.50	0.50	0.00	No work		
	154.00	167.00	R/S	1	13.00			0.50	0.50	3.25	0.9 PCS		
	167.00	179.80	R/S	0	12.80			0.50	0.50	0.00	Deck slab		
	179.80	195.00	R/S	1	15.20			0.50	0.50	3.80	0.9 PCS		
	195.00	212.00	R/S	1	17.00			0.50	0.50	4.25	0.9 PCS		
	212.00	231.00	R/S	0	19.00			0.50	0.50	0.00	No work		
	231.00	241.00	R/S	1	10.00			0.50	0.50	2.50	0.9 PCS		
	5th Cross Road (GKVK Double Rd to RKH 2nd Mn Rd)												
	LHS												
	0.00	26.00	L/S	1	26.00			0.50	0.50	6.50	0.9 PCS		
	26.00	30.00	L/S	1	4.00			0.50	0.50	1.00	1.2 BS		
	30.00	43.60	L/S	0	13.60			0.50	0.50	0.00	No work		
	43.60	60.00	L/S	1	16.40			0.50	0.50	4.10	0.9 PCS		
	60.00	75.00	L/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	75.00	90.00	L/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	90.00	105.00	L/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	105.00	120.00	L/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	120.00	135.00	L/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	135.00	150.00	L/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	150.00	165.00	L/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	165.00	180.00	L/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	180.00	199.00	L/S	1	19.00			0.50	0.50	4.75	0.9 PCS		
	199.00	210.00	L/S	1	11.00			0.50	0.50	2.75	Only desilt		
	210.00	227.50	L/S	1	17.50			0.50	0.50	4.38	0.9 PCS		
	RHS												
	0.00	15.00	R/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	15.00	30.00	R/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	30.00	45.00	R/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	45.00	68.00	R/S	1	23.00			0.50	0.50	5.75	0.9 PCS		
	68.00	73.00	R/S	0	5.00			0.50	0.50	0.00	Deck slab		
	73.00	90.00	R/S	0	17.00			0.50	0.50	0.00	No work		

BOQ Item No	Description Chainage		Side	Nos	L	B1	B2	Avg width	Depth	Quantity	Unit/ Remarks	Rate	Amount
	90.00	104.00	R/S	0	14.00			0.50	0.50	0.00	No work		
	104.00	120.00	R/S	1	16.00			0.50	0.50	4.00	0.9 PCS		
	120.00	135.00	R/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	135.00	150.00	R/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	150.00	165.00	R/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	165.00	180.00	R/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	180.00	195.00	R/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	195.00	205.00	R/S	1	10.00			0.50	0.50	2.50	0.9 PCS		
	205.00	220.00	R/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	220.00	227.50	R/S	1	7.50			0.50	0.50	1.88	0.9 PCS		
	6th Cross Road (GKVK Double Rd to RKH 2nd Mn Rd)												
	LHS												
	0.00	15.00	L/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	15.00	30.00	L/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	30.00	45.00	L/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	45.00	60.00	L/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	60.00	75.00	L/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	75.00	96.00	L/S	1	21.00			0.50	0.50	5.25	0.9 PCS		
	96.00	108.00	L/S	0	12.00			0.50	0.50	0.00	No work		
	108.00	120.00	L/S	1	12.00			0.50	0.50	3.00	0.9 PCS		
	120.00	135.00	L/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	135.00	150.00	L/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	150.00	165.00	L/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	165.00	180.00	L/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	180.00	199.00	L/S	1	19.00			0.50	0.50	4.75	0.9 PCS		
	199.00	210.00	L/S	1	11.00			0.50	0.50	2.75	0.9 PCS		
	210.00	221.50	L/S	1	11.50			0.50	0.50	2.88	0.9 PCS		
	RHS												
	0.00	15.00	R/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	15.00	30.00	R/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	30.00	45.00	R/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	45.00	60.00	R/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	60.00	75.00	R/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	75.00	90.00	R/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	90.00	105.00	R/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	105.00	120.00	R/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	120.00	135.00	R/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	135.00	150.00	R/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	150.00	165.00	R/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	165.00	180.00	R/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	180.00	195.00	R/S	1	15.00			0.50	0.50	3.75	0.9 PCS		
	195.00	205.00	R/S	1	10.00			0.50	0.50	2.50	0.9 PCS		
	205.00	221.50	R/S	1	16.50			0.50	0.50	4.13	0.9 PCS		
	Apoorva Enclave												
	Culvert Desilt												
				1	9.40			0.60	0.60	3.38			
	Apoorva Enclave												
	Culvert Desilt												
	254.50	256.30		1	9.50			0.60	1.00	5.70	1.5 BS Slab		
								Total Quantity		6980.37	Cum	234.00	16,33,406.14